

| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING | | | | | | FORM 3 AMENDED REPORT | | | | |
|--|------------------|-------------|--|--------------------------------|--|--|-----------------------------|-------|-------|--------|
| APPLICATION FOR PERMIT TO DRILL | | | | | | 1. WELL NAME and NUMBER GMBU W-16-9-16 | | | | |
| 2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/> | | | | | | 3. FIELD OR WILDCAT MONUMENT BUTTE | | | | |
| 4. TYPE OF WELL Oil Well Coalbed Methane Well: NO | | | | | | 5. UNIT or COMMUNITIZATION AGREEMENT NAME GMBU (GRRV) | | | | |
| 6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY | | | | | | 7. OPERATOR PHONE 435 646-4825 | | | | |
| 8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052 | | | | | | 9. OPERATOR E-MAIL mcrozier@newfield.com | | | | |
| 10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) UTU-64379 | | | 11. MINERAL OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/> | | | 12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/> | | | | |
| 13. NAME OF SURFACE OWNER (if box 12 = 'fee') | | | | | | 14. SURFACE OWNER PHONE (if box 12 = 'fee') | | | | |
| 15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') | | | | | | 16. SURFACE OWNER E-MAIL (if box 12 = 'fee') | | | | |
| 17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN') | | | 18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/> | | | 19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/> | | | | |
| 20. LOCATION OF WELL | FOOTAGES | | QTR-QTR | SECTION | TOWNSHIP | RANGE | MERIDIAN | | | |
| LOCATION AT SURFACE | 726 FNL 1924 FWL | | NENW | 21 | 9.0 S | 16.0 E | S | | | |
| Top of Uppermost Producing Zone | 180 FNL 2234 FWL | | NENW | 21 | 9.0 S | 16.0 E | S | | | |
| At Total Depth | 353 FSL 2559 FWL | | SESW | 16 | 9.0 S | 16.0 E | S | | | |
| 21. COUNTY DUCESNE | | | 22. DISTANCE TO NEAREST LEASE LINE (Feet) 353 | | 23. NUMBER OF ACRES IN DRILLING UNIT 20 | | | | | |
| | | | 25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 1022 | | 26. PROPOSED DEPTH MD: 6103 TVD: 5950 | | | | | |
| 27. ELEVATION - GROUND LEVEL 5980 | | | 28. BOND NUMBER WYB000493 | | 29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 437478 | | | | | |
| Hole, Casing, and Cement Information | | | | | | | | | | |
| String | Hole Size | Casing Size | Length | Weight | Grade & Thread | Max Mud Wt. | Cement | Sacks | Yield | Weight |
| SURF | 12.25 | 8.625 | 0 - 300 | 24.0 | J-55 ST&C | 8.3 | Class G | 138 | 1.17 | 15.8 |
| PROD | 7.875 | 5.5 | 0 - 6103 | 15.5 | J-55 LT&C | 8.3 | Premium Lite High Strength | 283 | 3.26 | 11.0 |
| | | | | | | | 50/50 Poz | 363 | 1.24 | 14.3 |
| ATTACHMENTS | | | | | | | | | | |
| VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES | | | | | | | | | | |
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER | | | | | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN | | | | | |
| <input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE) | | | | | <input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER | | | | | |
| <input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED) | | | | | <input checked="" type="checkbox"/> TOPOGRAPHICAL MAP | | | | | |
| NAME Mandie Crozier | | | | TITLE Regulatory Tech | | | PHONE 435 646-4825 | | | |
| SIGNATURE | | | | DATE 07/16/2012 | | | EMAIL mcrozier@newfield.com | | | |
| API NUMBER ASSIGNED 43013515790000 | | | | APPROVAL Permit Manager | | | | | | |

NEWFIELD PRODUCTION COMPANY
GMBU W-16-9-16
AT SURFACE: NE/NW SECTION 21, T9S R16E
DUCHESNE COUNTY, UTAH

TEN POINT DRILLING PROGRAM

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

| | |
|--------------------|--------------|
| Uinta | 0' – 1550' |
| Green River | 1550' |
| Wasatch | 6210' |
| Proposed TD | 6103' |

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:**

Green River Formation (Oil) 1550' – 6210'

Fresh water may be encountered in the Uinta Formation, but would not be expected below about 350'. All water shows and water bearing geologic units shall be reported to the geologic and engineering staff of the Vernal Office prior to running the next string of casing or before plugging orders are requested. All water shows must be reported within one (1) business day after being encountered.

All usable (<10,000 PPM TDS) water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling will be recorded by depth and adequately protected. This information shall be reported to the Vernal Office.

Detected water flows shall be sampled, analyzed, and reported to the geologic & engineering staff of the Vernal Office. The office may request additional water samples for further analysis. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required.

The following information is requested for water shows and samples where applicable:

| | |
|--|---|
| Location & Sampled Interval | Date Sampled |
| Flow Rate | Temperature |
| Hardness | pH |
| Water Classification (State of Utah) | Dissolved Calcium (Ca) (mg/l) |
| Dissolved Iron (Fe) (ug/l) | Dissolved Sodium (Na) (mg/l) |
| Dissolved Magnesium (Mg) (mg/l) | Dissolved Carbonate (CO ₃) (mg/l) |
| Dissolved Bicarbonate (NaHCO ₃) (mg/l) | Dissolved Chloride (Cl) (mg/l) |
| Dissolved Sulfate (SO ₄) (mg/l) | Dissolved Total Solids (TDS) (mg/l) |

4. **PROPOSED CASING PROGRAM**

a. Casing Design: GMBU W-16-9-16

| Size | Interval | | Weight | Grade | Coupling | Design Factors | | |
|--------------------------|----------|--------|--------|-------|----------|----------------|----------------|------------------|
| | Top | Bottom | | | | Burst | Collapse | Tension |
| Surface casing 8-5/8" | 0' | 300' | 24.0 | J-55 | STC | 2,950 17.53 | 1,370 14.35 | 244,000 33.89 |
| Prod casing 5-1/2" | 0' | 6,103' | 15.5 | J-55 | LTC | 4,810 2.48 | 4,040 2.08 | 217,000 2.29 |

Assumptions:

- 1) Surface casing max anticipated surface press (MASP) = Frac gradient – gas gradient
- 2) Prod casing MASP (production mode) = Pore pressure – gas gradient
- 3) All collapse calculations assume fully evacuated casing w/ gas gradient
- 4) All tension calculations assume air weight

Frac gradient at surface casing shoe = 13.0 ppg
 Pore pressure at surface casing shoe = 8.33 ppg
 Pore pressure at prod casing shoe = 8.33 ppg
 Gas gradient = 0.115 psi/ft

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing strings shall have a minimum of 1 (one) centralizer on each of the bottom three (3) joints.

b. Cementing Design: GMBU W-16-9-16

| Job | Fill | Description | Sacks | OH Excess* | Weight (ppg) | Yield (ft ³ /sk) |
|---------------------|--------|-------------------------------------|-----------------|---------------|-----------------|--------------------------------|
| | | | ft ³ | | | |
| Surface casing | 300' | Class G w/ 2% CaCl | 138 161 | 30% | 15.8 | 1.17 |
| Prod casing Lead | 4,103' | Prem Lite II w/ 10% gel + 3% KCl | 283 924 | 30% | 11.0 | 3.26 |
| Prod casing Tail | 2,000' | 50/50 Poz w/ 2% gel + 3% KCl | 363 451 | 30% | 14.3 | 1.24 |

*Actual volume pumped will be 15% over the caliper log

- Compressive strength of lead cement: 1800 psi @ 24 hours, 2250 psi @ 72 hours
- Compressive strength of tail cement: 2500 psi @ 24 hours

Hole Sizes: A 12-1/4" hole will be drilled for the 8-5/8" surface casing. A 7-7/8" hole will be drilled for the 5-1/2" production casing.

The 8-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operation the cement does not circulate to surface, or if the cement level should fall back more than 8 feet from surface, then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

5. **MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to **Exhibit C** for a diagram of BOP equipment that will be used on this well.

6. **TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

From surface to ± 300 feet will be drilled with an air/mist system. The air rig is equipped with a 6 1/2" blooie line that is straight run and securely anchored. The blooie line is used with a discharge less than 100 ft from the wellbore in order to minimize the well pad size. The blooie line is not equipped with an automatic igniter or continuous pilot light and the compressor is located less than 100 ft from the well bore due to the low possibility of combustion with the air dust mixture. The trailer mounted compressor (capacity of 2000 CFM) has a safety shut-off valve which is located 15 feet from the air rig. A truck with 70 bbls of water is on stand by to be used as kill fluid, if necessary. From about ± 300 feet to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCl substitute additive. This additive will be identified in the APD and reviewed to determine if the reserve pit shall be lined. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

Newfield Production will **visually** monitor pit levels and flow from the well during drilling operations.

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. **TESTING, LOGGING AND CORING PROGRAMS:**

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 300' +/-, and a Compensated Neutron-Formation Density Log from TD to 3500' +/- . A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.

9. **ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated


bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.

10. **ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

It is anticipated that the drilling operations will commence the fourth quarter of 2012, and take approximately seven (7) days from spud to rig release.

T9S, R16E, S.L.B.&M.**NEWFIELD EXPLORATION COMPANY**


WELL LOCATION, W-16-9-16, LOCATED
AS SHOWN IN THE NE 1/4 NW 1/4 OF
SECTION 21, T9S, R16E, S.L.B.&M.
DUCESNE COUNTY, UTAH.

**NOTES:**

1. Well footages are measured at right angles to the Section Lines.
2. Bearings are based on Global Positioning Satellite observations.




THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS
MADE BY ME OR UNDER MY SUPERVISION AND THAT
THE SAME ARE TRUE AND CORRECT TO THE BEST
OF MY KNOWLEDGE AND BELIEF.

**TRI STATE LAND SURVEYING & CONSULTING**

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

| | | |
|----------------------------|-------------------|----------|
| DATE SURVEYED: 01-10-12 | SURVEYED BY: C.S. | VERSION: |
| DATE DRAWN: 05-14-12 | DRAWN BY: M.W. | V1 |
| REVISED: 07-12-12 M.W. | SCALE: 1" = 1000' | |



◆ = SECTION CORNERS LOCATED


BASIS OF ELEV; Elevations are based on
an N.G.S. OPUS Correction. LOCATION:
LAT. 40°04'09.56" LONG. 110°00'43.28"
(Tristate Aluminum Cap) Elev. 5281.57'

W-16-9-16
(Surface Location) NAD 83
LATITUDE = 40° 01' 17.85"
LONGITUDE = 110° 07' 36.83"

RECEIVED: July 16, 2012


T9S, R16E, S.L.B.&M.**NEWFIELD EXPLORATION COMPANY**

TARGET BOTTOM HOLE, W-16-9-16,
LOCATED AS SHOWN IN THE SE 1/4
SW 1/4 OF SECTION 16, T9S, R16E,
S.L.B.&M. DUCHESNE COUNTY, UTAH.

**NOTES:**


1. Well footages are measured at right angles to the Section Lines.
2. Bearings are based on Global Positioning Satellite observations.
3. The Center of Pattern footages are 100' FSL & 2410' FWL.
4. The Bottom of Hole footages are 353' FSL & 2559' FWL.

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS
MADE BY ME OR UNDER MY SUPERVISION AND THAT
THE SAME ARE TRUE AND CORRECT TO THE BEST
OF MY KNOWLEDGE AND BELIEF.

**TRI STATE LAND SURVEYING & CONSULTING**

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

| | | |
|----------------------------|-------------------|----------|
| DATE SURVEYED: 01-10-12 | SURVEYED BY: C.S. | VERSION: |
| DATE DRAWN: 05-14-12 | DRAWN BY: M.W. | V1 |
| REVISED: 07-12-12 M.W. | SCALE: 1" = 1000' | |




BASIS OF ELEV; Elevations are based on
an N.G.S. OPUS Correction. LOCATION:
LAT. 40°04'09.56" LONG. 110°00'43.28"
(Tristate Aluminum Cap) Elev. 5281.57'



= SECTION CORNERS LOCATED

RECEIVED: July 16, 2012

Access Road Map



**Tri State
Land Surveying, Inc.**

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

3-21-9-16 (Existing Well)
W-16-9-16 (Proposed Well)
H-21-9-16 (Proposed Well)

SEC. 21, T9S, R16E, S.L.B.&M. Duchesne County, UT.

DRAWN BY: D.C.R. REVISED: 07-12-12 D.C.R. VERSION:

DATE: 03-29-2012

SCALE: 1:100,000


V1

TOPOGRAPHIC MAP

SHEET

A

Access Road Map



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518

**NEWFIELD EXPLORATION COMPANY**

3-21-9-16 (Existing Well)
W-16-9-16 (Proposed Well)
H-21-9-16 (Proposed Well)
SEC. 21, T9S, R16E, S.L.B.&M. Duchesne County, UT.

DRAWN BY: D.C.R. REVISED: 07-12-12 D.C.R. VERSION:

DATE: 03-29-2012

SCALE: 1" = 2,000'


V1

TOPOGRAPHIC MAP

SHEET

B

Proposed Pipeline Map



3-21-9-16 (Existing Well)
W-16-9-16 (Proposed Well)
H-21-9-16 (Proposed Well)

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

3-21-9-16 (Existing Well)
W-16-9-16 (Proposed Well)
H-21-9-16 (Proposed Well)
SEC. 21, T9S, R16E, S.L.B.&M. Duchesne County, UT.

DRAWN BY: D.C.R. REVISED: 07-12-12 D.C.R. VERSION:

DATE: 03-29-2012

SCALE: 1" = 2,000'

V1


TOPOGRAPHIC MAP

SHEET

C

Exhibit "B" Map

3-21-9-16 (Existing Well)
W-16-9-16 (Proposed Well)
H-21-9-16 (Proposed Well)

**Legend**

- 1 Mile Radius
● Pad Location

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518

**NEWFIELD EXPLORATION COMPANY**

3-21-9-16 (Existing Well)
W-16-9-16 (Proposed Well)
H-21-9-16 (Proposed Well)
SEC. 21, T9S, R16E, S.L.B.&M. Duchesne County, UT.

| | | | | |
|-----------|-------------|----------|-----------------|-----------|
| DRAWN BY: | D.C.R. | REVISED: | 07-12-12 D.C.R. | VERSION: |
| DATE: | 03-29-2012 | | | V1 |
| SCALE: | 1" = 2,000' | | | |

TOPOGRAPHIC MAP

SHEET

D



NEWFIELD EXPLORATION

**USGS Myton SW (UT)
SECTION 21 T9S, R16E
W-16-9-16**

Wellbore #1

Plan: Design #1

Standard Planning Report

14 May, 2012





Payzone Directional Planning Report



| | | | |
|------------------|----------------------------|-------------------------------------|---|
| Database: | EDM 2003.21 Single User Db | Local Co-ordinate Reference: | Well W-16-9-16 |
| Company: | NEWFIELD EXPLORATION | TVD Reference: | W-16-9-16 @ 5992.0ft (Original Well Elev) |
| Project: | USGS Myton SW (UT) | MD Reference: | W-16-9-16 @ 5992.0ft (Original Well Elev) |
| Site: | SECTION 21 T9S, R16E | North Reference: | True |
| Well: | W-16-9-16 | Survey Calculation Method: | Minimum Curvature |
| Wellbore: | Wellbore #1 | | |
| Design: | Design #1 | | |

| | | | |
|--------------------|--|----------------------|----------------|
| Project | USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA | | |
| Map System: | US State Plane 1983 | System Datum: | Mean Sea Level |
| Geo Datum: | North American Datum 1983 | | |
| Map Zone: | Utah Central Zone | | |

| | | | | |
|------------------------------|----------------------|---------------------|-----------------|------------------------------------|
| Site | SECTION 21 T9S, R16E | | | |
| Site Position: | | Northing: | 7,178,195.78 ft | Latitude: 40° 1' 4.650 N |
| From: | Lat/Long | Easting: | 2,023,590.50 ft | Longitude: 110° 7' 54.390 W |
| Position Uncertainty: | 0.0 ft | Slot Radius: | " | Grid Convergence: 0.88 ° |

| | | | | |
|-----------------------------|---|----------------------------|------------------|---------------------------------|
| Well | W-16-9-16, SHL LAT: 40 01 17.85 LONG: -110 07 36.83 | | | |
| Well Position | +N/-S | 1,335.5 ft | Northing: | 7,179,552.14 ft |
| | +E/-W | 1,366.1 ft | Easting: | 2,024,935.92 ft |
| Position Uncertainty | 0.0 ft | Wellhead Elevation: | 5,992.0 ft | Ground Level: 5,980.0 ft |

| | | | | | |
|------------------|-------------------|--------------------|------------------------|----------------------|----------------------------|
| Wellbore | Wellbore #1 | | | | |
| Magnetics | Model Name | Sample Date | Declination (°) | Dip Angle (°) | Field Strength (nT) |
| | IGRF2010 | 5/14/2012 | 11.22 | 65.74 | 52,155 |

| | | | | |
|--------------------------|------------------------------|-------------------|----------------------|----------------------|
| Design | Design #1 | | | |
| Audit Notes: | | | | |
| Version: | Phase: | PROTOTYPE | Tie On Depth: | 0.0 |
| Vertical Section: | Depth From (TVD) (ft) | +N/-S (ft) | +E/-W (ft) | Direction (°) |
| | 4,810.0 | 0.0 | 0.0 | 29.60 |

| Plan Sections | | | | | | | | | | |
|----------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|----------------------|---------------------|---------|---------------|
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) | TFO (°) | Target |
| 0.0 | 0.00 | 0.00 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 600.0 | 0.00 | 0.00 | 600.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1,561.1 | 14.42 | 29.60 | 1,551.0 | 104.6 | 59.4 | 1.50 | 1.50 | 0.00 | 29.60 | |
| 4,926.1 | 14.42 | 29.60 | 4,810.0 | 833.0 | 473.3 | 0.00 | 0.00 | 0.00 | 0.00 | W-16-9-16 TGT |
| 6,103.1 | 14.42 | 29.60 | 5,950.0 | 1,087.8 | 618.1 | 0.00 | 0.00 | 0.00 | 0.00 | |



Payzone Directional

Planning Report



| | | | |
|------------------|----------------------------|-------------------------------------|---|
| Database: | EDM 2003.21 Single User Db | Local Co-ordinate Reference: | Well W-16-9-16 |
| Company: | NEWFIELD EXPLORATION | TVD Reference: | W-16-9-16 @ 5992.0ft (Original Well Elev) |
| Project: | USGS Myton SW (UT) | MD Reference: | W-16-9-16 @ 5992.0ft (Original Well Elev) |
| Site: | SECTION 21 T9S, R16E | North Reference: | True |
| Well: | W-16-9-16 | Survey Calculation Method: | Minimum Curvature |
| Wellbore: | Wellbore #1 | | |
| Design: | Design #1 | | |

| Planned Survey | | | | | | | | | |
|---------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|----------------------|---------------------|
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
| 0.0 | 0.00 | 0.00 | 0.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 100.0 | 0.00 | 0.00 | 100.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 200.0 | 0.00 | 0.00 | 200.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 300.0 | 0.00 | 0.00 | 300.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 400.0 | 0.00 | 0.00 | 400.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 500.0 | 0.00 | 0.00 | 500.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 600.0 | 0.00 | 0.00 | 600.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 700.0 | 1.50 | 29.60 | 700.0 | 1.1 | 0.6 | 1.3 | 1.50 | 1.50 | 0.00 |
| 800.0 | 3.00 | 29.60 | 799.9 | 4.6 | 2.6 | 5.2 | 1.50 | 1.50 | 0.00 |
| 900.0 | 4.50 | 29.60 | 899.7 | 10.2 | 5.8 | 11.8 | 1.50 | 1.50 | 0.00 |
| 1,000.0 | 6.00 | 29.60 | 999.3 | 18.2 | 10.3 | 20.9 | 1.50 | 1.50 | 0.00 |
| 1,100.0 | 7.50 | 29.60 | 1,098.6 | 28.4 | 16.1 | 32.7 | 1.50 | 1.50 | 0.00 |
| 1,200.0 | 9.00 | 29.60 | 1,197.5 | 40.9 | 23.2 | 47.0 | 1.50 | 1.50 | 0.00 |
| 1,300.0 | 10.50 | 29.60 | 1,296.1 | 55.6 | 31.6 | 64.0 | 1.50 | 1.50 | 0.00 |
| 1,400.0 | 12.00 | 29.60 | 1,394.2 | 72.6 | 41.2 | 83.5 | 1.50 | 1.50 | 0.00 |
| 1,500.0 | 13.50 | 29.60 | 1,491.7 | 91.8 | 52.1 | 105.5 | 1.50 | 1.50 | 0.00 |
| 1,561.1 | 14.42 | 29.60 | 1,551.0 | 104.6 | 59.4 | 120.3 | 1.50 | 1.50 | 0.00 |
| 1,600.0 | 14.42 | 29.60 | 1,588.7 | 113.0 | 64.2 | 130.0 | 0.00 | 0.00 | 0.00 |
| 1,700.0 | 14.42 | 29.60 | 1,685.5 | 134.6 | 76.5 | 154.9 | 0.00 | 0.00 | 0.00 |
| 1,800.0 | 14.42 | 29.60 | 1,782.4 | 156.3 | 88.8 | 179.8 | 0.00 | 0.00 | 0.00 |
| 1,900.0 | 14.42 | 29.60 | 1,879.2 | 177.9 | 101.1 | 204.7 | 0.00 | 0.00 | 0.00 |
| 2,000.0 | 14.42 | 29.60 | 1,976.1 | 199.6 | 113.4 | 229.6 | 0.00 | 0.00 | 0.00 |
| 2,100.0 | 14.42 | 29.60 | 2,072.9 | 221.2 | 125.7 | 254.5 | 0.00 | 0.00 | 0.00 |
| 2,200.0 | 14.42 | 29.60 | 2,169.8 | 242.9 | 138.0 | 279.3 | 0.00 | 0.00 | 0.00 |
| 2,300.0 | 14.42 | 29.60 | 2,266.6 | 264.5 | 150.3 | 304.2 | 0.00 | 0.00 | 0.00 |
| 2,400.0 | 14.42 | 29.60 | 2,363.5 | 286.2 | 162.6 | 329.1 | 0.00 | 0.00 | 0.00 |
| 2,500.0 | 14.42 | 29.60 | 2,460.3 | 307.8 | 174.9 | 354.0 | 0.00 | 0.00 | 0.00 |
| 2,600.0 | 14.42 | 29.60 | 2,557.2 | 329.5 | 187.2 | 378.9 | 0.00 | 0.00 | 0.00 |
| 2,700.0 | 14.42 | 29.60 | 2,654.0 | 351.1 | 199.5 | 403.8 | 0.00 | 0.00 | 0.00 |
| 2,800.0 | 14.42 | 29.60 | 2,750.9 | 372.8 | 211.8 | 428.7 | 0.00 | 0.00 | 0.00 |
| 2,900.0 | 14.42 | 29.60 | 2,847.7 | 394.4 | 224.1 | 453.6 | 0.00 | 0.00 | 0.00 |
| 3,000.0 | 14.42 | 29.60 | 2,944.6 | 416.1 | 236.4 | 478.5 | 0.00 | 0.00 | 0.00 |
| 3,100.0 | 14.42 | 29.60 | 3,041.4 | 437.7 | 248.7 | 503.4 | 0.00 | 0.00 | 0.00 |
| 3,200.0 | 14.42 | 29.60 | 3,138.3 | 459.4 | 261.0 | 528.3 | 0.00 | 0.00 | 0.00 |
| 3,300.0 | 14.42 | 29.60 | 3,235.1 | 481.0 | 273.3 | 553.2 | 0.00 | 0.00 | 0.00 |
| 3,400.0 | 14.42 | 29.60 | 3,332.0 | 502.7 | 285.6 | 578.1 | 0.00 | 0.00 | 0.00 |
| 3,500.0 | 14.42 | 29.60 | 3,428.8 | 524.3 | 297.9 | 603.0 | 0.00 | 0.00 | 0.00 |
| 3,600.0 | 14.42 | 29.60 | 3,525.7 | 545.9 | 310.2 | 627.9 | 0.00 | 0.00 | 0.00 |
| 3,700.0 | 14.42 | 29.60 | 3,622.5 | 567.6 | 322.5 | 652.8 | 0.00 | 0.00 | 0.00 |
| 3,800.0 | 14.42 | 29.60 | 3,719.4 | 589.2 | 334.8 | 677.7 | 0.00 | 0.00 | 0.00 |
| 3,900.0 | 14.42 | 29.60 | 3,816.2 | 610.9 | 347.1 | 702.6 | 0.00 | 0.00 | 0.00 |
| 4,000.0 | 14.42 | 29.60 | 3,913.1 | 632.5 | 359.4 | 727.5 | 0.00 | 0.00 | 0.00 |
| 4,100.0 | 14.42 | 29.60 | 4,009.9 | 654.2 | 371.7 | 752.4 | 0.00 | 0.00 | 0.00 |
| 4,200.0 | 14.42 | 29.60 | 4,106.8 | 675.8 | 384.0 | 777.3 | 0.00 | 0.00 | 0.00 |
| 4,300.0 | 14.42 | 29.60 | 4,203.6 | 697.5 | 396.3 | 802.2 | 0.00 | 0.00 | 0.00 |
| 4,400.0 | 14.42 | 29.60 | 4,300.5 | 719.1 | 408.6 | 827.1 | 0.00 | 0.00 | 0.00 |
| 4,500.0 | 14.42 | 29.60 | 4,397.3 | 740.8 | 420.9 | 852.0 | 0.00 | 0.00 | 0.00 |
| 4,600.0 | 14.42 | 29.60 | 4,494.2 | 762.4 | 433.2 | 876.9 | 0.00 | 0.00 | 0.00 |
| 4,700.0 | 14.42 | 29.60 | 4,591.0 | 784.1 | 445.5 | 901.8 | 0.00 | 0.00 | 0.00 |
| 4,800.0 | 14.42 | 29.60 | 4,687.9 | 805.7 | 457.8 | 926.7 | 0.00 | 0.00 | 0.00 |
| 4,900.0 | 14.42 | 29.60 | 4,784.7 | 827.4 | 470.1 | 951.6 | 0.00 | 0.00 | 0.00 |
| 4,926.1 | 14.42 | 29.60 | 4,810.0 | 833.0 | 473.3 | 958.1 | 0.00 | 0.00 | 0.00 |
| 5,000.0 | 14.42 | 29.60 | 4,881.6 | 849.0 | 482.4 | 976.5 | 0.00 | 0.00 | 0.00 |
| 5,100.0 | 14.42 | 29.60 | 4,978.4 | 870.7 | 494.7 | 1,001.4 | 0.00 | 0.00 | 0.00 |



Payzone Directional

Planning Report



| | | | |
|------------------|----------------------------|-------------------------------------|---|
| Database: | EDM 2003.21 Single User Db | Local Co-ordinate Reference: | Well W-16-9-16 |
| Company: | NEWFIELD EXPLORATION | TVD Reference: | W-16-9-16 @ 5992.0ft (Original Well Elev) |
| Project: | USGS Myton SW (UT) | MD Reference: | W-16-9-16 @ 5992.0ft (Original Well Elev) |
| Site: | SECTION 21 T9S, R16E | North Reference: | True |
| Well: | W-16-9-16 | Survey Calculation Method: | Minimum Curvature |
| Wellbore: | Wellbore #1 | | |
| Design: | Design #1 | | |

| Planned Survey | | | | | | | | | |
|---------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|----------------------|---------------------|
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
| 5,200.0 | 14.42 | 29.60 | 5,075.3 | 892.3 | 507.0 | 1,026.3 | 0.00 | 0.00 | 0.00 |
| 5,300.0 | 14.42 | 29.60 | 5,172.2 | 914.0 | 519.3 | 1,051.2 | 0.00 | 0.00 | 0.00 |
| 5,400.0 | 14.42 | 29.60 | 5,269.0 | 935.6 | 531.6 | 1,076.1 | 0.00 | 0.00 | 0.00 |
| 5,500.0 | 14.42 | 29.60 | 5,365.9 | 957.3 | 543.9 | 1,101.0 | 0.00 | 0.00 | 0.00 |
| 5,600.0 | 14.42 | 29.60 | 5,462.7 | 978.9 | 556.2 | 1,125.9 | 0.00 | 0.00 | 0.00 |
| 5,700.0 | 14.42 | 29.60 | 5,559.6 | 1,000.5 | 568.5 | 1,150.8 | 0.00 | 0.00 | 0.00 |
| 5,800.0 | 14.42 | 29.60 | 5,656.4 | 1,022.2 | 580.8 | 1,175.7 | 0.00 | 0.00 | 0.00 |
| 5,900.0 | 14.42 | 29.60 | 5,753.3 | 1,043.8 | 593.1 | 1,200.6 | 0.00 | 0.00 | 0.00 |
| 6,000.0 | 14.42 | 29.60 | 5,850.1 | 1,065.5 | 605.4 | 1,225.5 | 0.00 | 0.00 | 0.00 |
| 6,103.1 | 14.42 | 29.60 | 5,950.0 | 1,087.8 | 618.1 | 1,251.1 | 0.00 | 0.00 | 0.00 |

API Well Number: 43013515790000





Project: USGS Myton SW (UT)
 Site: SECTION 21 T9S, R16E
 Well: W-16-9-16
 Wellbore: Wellbore #1
 Design: Design #1



Azimuths to True North
 Magnetic North: 11.22°

Magnetic Field
 Strength: 52154.5snT
 Dip Angle: 65.74°
 Date: 5/14/2012
 Model: IGRF2010

KOP @ 600'
 DOGLEG RATE 1.5 DEG/100
 TARGET RADIUS IS 75'



WELLBORE TARGET DETAILS

| Name | TVD | +N/-S | +E/-W | Shape |
|---------------|--------|-------|-------|-----------------------|
| W-16-9-16 TGT | 4810.0 | 833.0 | 473.3 | Circle (Radius: 75.0) |

SECTION DETAILS

| Sec | MD | Inc | Azi | TVD | +N/-S | +E/-W | DLeg | TFace | VSec | Target |
|-----|--------|-------|-------|--------|--------|-------|------|-------|--------|---------------|
| 1 | 0.0 | 0.00 | 0.00 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.0 | |
| 2 | 600.0 | 0.00 | 0.00 | 600.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.0 | |
| 3 | 1561.1 | 14.42 | 29.60 | 1551.0 | 104.6 | 59.4 | 1.50 | 29.60 | 120.3 | |
| 4 | 4926.1 | 14.42 | 29.60 | 4810.0 | 833.0 | 473.3 | 0.00 | 0.00 | 958.1 | W-16-9-16 TGT |
| 5 | 6103.1 | 14.42 | 29.60 | 5950.0 | 1087.8 | 618.1 | 0.00 | 0.00 | 1251.1 | |



**NEWFIELD PRODUCTION COMPANY
GMBU W-16-9-16
AT SURFACE: NE/NW SECTION 21, T9S R16E
DUCHESNE COUNTY, UTAH**

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. EXISTING ROADS

See attached Topographic Map "A"

To reach Newfield Production Company well location site GMBU W-16-9-16 located in the NE 1/4 NW 1/4 Section 21, T9S, R16E, Duchesne County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 – 1.4 miles \pm to the junction of this highway and UT State Hwy 53; proceed in a southeasterly direction – 10.0 miles \pm to it's junction with an existing road to the southwest; proceed in a southwesterly direction – 6.7 miles \pm to it's junction with an existing road to the north; proceed in a northerly direction – 228' \pm to the existing 3-21-9-16 well location.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal. Any necessary fill material for repair will be purchase and hauled from private sources.

2. PLANNED ACCESS ROAD

There is no proposed access road for this location. The proposed well will be drilled directionaly off of the existing 3-21-9-16 well pad. See attached **Topographic Map "B"**.

There will be **no** culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

3. LOCATION OF EXISTING WELLS

Refer to Exhibit "B".

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Newfield Production will transport water by truck from nearest water source as determined by a Newfield representative for the purpose of drilling the above mentioned well. The available water sources are as follows:

Johnson Water District
Water Right : 43-10136

Maurice Harvey Pond
Water Right: 47-1358

Neil Moon Pond
Water Right: 43-11787

Newfield Collector Well
Water Right: 47-1817 (A30414DVA, contracted with the Duchesne County Conservancy District).

There will be no water well drilled at this site.

6. **SOURCE OF CONSTRUCTION MATERIALS**

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

8. **ANCILLARY FACILITIES**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT**

See attached Location Layout Sheet.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Existing fences to be crossed by the access road will be braced and tied off before cutting so as to prevent slacking in the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM specifications.

10. **PLANS FOR RESTORATION OF SURFACE:**

- a) Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

- b) Dry Hole Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP** – State of Utah.

12. **OTHER ADDITIONAL INFORMATION**

The Archaeological Resource Survey and Paleontological Resource Survey for this area are attached. State of Utah Antiquities Project Permit #U-05-MQ-0709b 7/25/05, prepared by Montgomery Archaeological

Consultants. Paleontological Resource Survey prepared by, Wade E. Miller, 11/10/05. See attached report cover pages, Exhibit "D".

Newfield Production Company requests 1,580' of buried water line be granted. **Refer to Topographic Map "C"**. The proposed pipelines will be constructed using the following procedures as outlined in the Greater Monument Butte Green River Development SOP.

In the event that the proposed well is converted to a water injection well, a Sundry Notice 3160-5 form will be applied for through the Bureau of Land Management field office.

Water Disposal

After first production, if the production water meets quality guidelines, it will be transported to the Ashley, Monument Butte, Jonah, South Wells Draw and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project. Water not meeting quality criteria, will be disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E), Federally approved surface disposal facilities or at a State of Utah approved surface disposal facilities.

Additional Surface Stipulations

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

Details of the On-Site Inspection

The proposed GMBU W-16-9-16 was on-sited on 5/18/12. The following were present; Corie Miller (Newfield Production), Janna Simonsen (Bureau of Land Management), and Dave Gordon (Bureau of Land Management).

Hazardous Material Declaration

Newfield Production Company guarantees that during the drilling and completion of the GMBU W-16-9-16, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the GMBU W-16-9-16, Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

13. **LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:**
Representative

Name: Corie Miller
Address: Newfield Production Company
Route 3, Box 3630
Myton, UT 84052
Telephone: (435) 646-3721

Certification

Please be advised that NEWFIELD PRODUCTION COMPANY is considered to be the operator of well #W-16-9-16, Section 21, Township 9S, Range 16E: Lease UTU-64379 Duchesne County, Utah: and is


responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by, Federal Bond #WYB000493.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.

7/30/12
Date

Mandie Crozier
Regulatory Analyst
Newfield Production Company

Typical 2M BOP stack configuration



2M CHOKE MANIFOLD EQUIPMENT - CONFIGURATION OF CHOKES MAY VARY

NEWFIELD EXPLORATION COMPANY

WELL PAD INTERFERENCE PLAT

3-21-9-16 (Existing Well)

W-16-9-16 (Proposed Well)

H-21-9-16 (Proposed Well)

Pad Location: NENW Section 21, T9S, R16E, S.L.B.&M.



TOP HOLE FOOTAGES

W-16-9-16 (PROPOSED)
726' FNL & 1924' FWL

H-21-9-16 (PROPOSED)
726' FNL & 1945' FWL

BOTTOM HOLE FOOTAGES

W-16-9-16 (PROPOSED)
353' FSL & 2559' FWL

H-21-9-16 (PROPOSED)
1505' FNL & 2434' FEL

CENTER OF PATTERN FOOTAGES

W-16-9-16 (PROPOSED)
100' FSL & 2410' FWL

H-21-9-16 (PROPOSED)
1358' FNL & 2701' FWL

Note:

Bearings are based
on GPS Observations.

RELATIVE COORDINATES From Top Hole to C.O.P.

| WELL | NORTH | EAST |
|-----------|-------|------|
| W-16-9-16 | 833' | 473' |
| H-21-9-16 | -620' | 765' |

RELATIVE COORDINATES From Top Hole to Bottom Hole


| WELL | NORTH | EAST |
|-----------|--------|------|
| W-16-9-16 | 1,088' | 618' |
| H-21-9-16 | -764' | 943' |

LATITUDE & LONGITUDE Surface position of Wells (NAD 83)



| WELL | LATITUDE | LONGITUDE |
|-----------|----------------|-----------------|
| 3-21-9-16 | 40° 01' 17.86" | 110° 07' 37.10" |
| W-16-9-16 | 40° 01' 17.85" | 110° 07' 36.83" |
| H-21-9-16 | 40° 01' 17.85" | 110° 07' 36.56" |

| | | |
|-------------------|--------------------------|----------|
| SURVEYED BY: C.S. | DATE SURVEYED: 01-10-12 | VERSION: |
| DRAWN BY: M.W. | DATE DRAWN: 05-14-12 | V1 |
| SCALE: 1" = 60' | REVISED: M.W. - 07-12-12 | |

Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078



RECEIVED: July 16, 2012

NEWFIELD EXPLORATION COMPANY**LOCATION LAYOUT****3-21-9-16 (Existing Well)****W-16-9-16 (Proposed Well)****H-21-9-16 (Proposed Well)***Pad Location: NENW Section 21, T9S, R16E, S.L.B.&M.***NOTE:**

The topsoil & excess material areas are calculated as being mounds containing 1,690 cubic yards of dirt (a 10% fluff factor is included). The mound areas are calculated with push slopes of 1.5:1 & fall slopes of 1.5:1.





Note:

Topsoil to be Stripped From All New Construction Areas and Proposed Stock Pile Locations

| | | |
|-------------------|--------------------------|----------|
| SURVEYED BY: C.S. | DATE SURVEYED: 01-10-12 | VERSION: |
| DRAWN BY: M.W. | DATE DRAWN: 03-26-12 | V1 |
| SCALE: 1" = 60' | REVISED: M.W. - 07-12-12 | |

Tri State (435) 781-2501
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: July 16, 2012

NEWFIELD EXPLORATION COMPANY***CROSS SECTIONS******3-21-9-16 (Existing Well)******W-16-9-16 (Proposed Well)******H-21-9-16 (Proposed Well)****Pad Location: NENW Section 21, T9S, R16E, S.L.B.&M.*

NOTE:
UNLESS OTHERWISE
NOTED ALL CUT/FILL
SLOPES ARE AT 1.5:1



ESTIMATED EARTHWORK QUANTITIES
(No Shrink or swell adjustments have been used)
(Expressed in Cubic Yards)

| ITEM | CUT | FILL | 6" TOPSOIL | EXCESS |
|--------|-------|------|--|--------|
| PAD | 610 | 0 | Topsoil is not included in Pad Cut | 610 |
| PIT | 690 | 0 | | 690 |
| TOTALS | 1,300 | 0 | 240 | 1,300 |

| | | |
|-------------------|--------------------------|----------|
| SURVEYED BY: C.S. | DATE SURVEYED: 01-10-12 | VERSION: |
| DRAWN BY: M.W. | DATE DRAWN: 03-26-12 | V1 |
| SCALE: 1" = 60' | REVISED: M.W. - 07-12-12 | |

Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: July 16, 2012

NEWFIELD EXPLORATION COMPANY**TYPICAL RIG LAYOUT****3-21-9-16 (Existing Well)****W-16-9-16 (Proposed Well)****H-21-9-16 (Proposed Well)***Pad Location: NENW Section 21, T9S, R16E, S.L.B.&M.*

Note:
Flare pit is to be
located a Minimum
of 100' from the
Proposed Well Head.

| | | |
|-------------------|--------------------------|----------|
| SURVEYED BY: C.S. | DATE SURVEYED: 01-10-12 | VERSION: |
| DRAWN BY: M.W. | DATE DRAWN: 03-26-12 | V1 |
| SCALE: 1" = 60' | REVISED: M.W. - 07-12-12 | |

Tri State
Land Surveying, Inc.
(435) 781-2501
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: July 16, 2012

VIA ELECTRONIC DELIVERY



July 23, 2012

State of Utah, Division of Oil, Gas and Mining
ATTN: Diana Mason
P.O. Box 145801
Salt Lake City, UT 84114-5801

RE: Directional Drilling
GMBU W-16-9-16
Greater Monument Butte (Green River) Unit

Surface Hole: T9S-R16E Section 21: NENW (UTU-64379)
726' FNL 1924' FWL

At Target: T9S-R16E Section 16: SESW (UTU-16532)
353' FSL 2559' FWL

Duchesne County, Utah

Dear Ms. Mason:

Pursuant to the filing by Newfield Production Company (NPC) of an Application for Permit to Drill the above referenced well dated 7/19/2012, a copy of which is attached, and in accordance with Oil and Gas Conservation Rule R649-3-11, NPC hereby submits this letter as notice of our intention to directionally drill this well.

The surface hole and target locations of this well are both within the boundaries of the Greater Monument Butte Unit (UTU-87538X), of which Newfield certifies that it is the operator. Further, Newfield certifies that all lands within 460 feet of the entire directional well bore are within the Greater Monument Butte Unit.

NPC is permitting this well as a directional well in order to mitigate surface disturbance by utilizing pre-existing roads and pipelines.

NPC hereby requests our application for permit to drill be granted pursuant to R649-3-11. If you have any questions or require further information, please contact the undersigned at 303-383-4121 or by email at lburget@newfield.com. Your consideration in this matter is greatly appreciated.

Sincerely,
Newfield Production Company

A handwritten signature in cursive script that reads "Leslie Burget".

Leslie Burget
Land Associate

Form 3160-3
(August 2007)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0136
Expires July 31, 2010

APPLICATION FOR PERMIT TO DRILL OR REENTER

| | | |
|--|---|---|
| 1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER | | 5. Lease Serial No. UTU64379 |
| 1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone | | 6. If Indian, Allottee or Tribe Name |
| 2. Name of Operator NEWFIELD PRODUCTION COMPANY Contact: MANDIE CROZIER Email: mcrozier@newfield.com | | 7. If Unit or CA Agreement, Name and No. GREATER MONUMENT |
| 3a. Address ROUTE #3 BOX 3630 MYTON, UT 84052 | 3b. Phone No. (include area code) Ph: 435-646-4825 Fx: 435-646-3031 | 8. Lease Name and Well No. GMBU W-16-9-16 |
| 4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NENW 726FNL 1924FWL At proposed prod. zone SESW 353FSL 2559FWL | | 9. API Well No. |
| 14. Distance in miles and direction from nearest town or post office* 18.2 | 10. Field and Pool, or Exploratory MONUMENT BUTTE | 11. Sec., T., R., M., or Blk. and Survey or Area Sec 21 T9S R16E Mer SLB |
| 15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 353' | 12. County or Parish DUCHESNE | 13. State UT |
| 16. No. of Acres in Lease 1626.30 | 17. Spacing Unit dedicated to this well 20.00 | |
| 18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 1022' | 19. Proposed Depth 6103 MD 5950 TVD | 20. BLM/BIA Bond No. on file WYB000493 |
| 21. Elevations (Show whether DF, KB, RT, GL, etc.) 5980 GL | 22. Approximate date work will start 10/31/2012 | 23. Estimated duration 7 DAYS |

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- | | |
|---|--|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

| | | |
|--|---|--------------------|
| 25. Signature (Electronic Submission) | Name (Printed/Typed) MANDIE CROZIER Ph: 435-646-4825 | Date 07/19/2012 |
| Title REGULATORY ANALYST | | |
| Approved by (Signature) | Name (Printed/Typed) | Date |
| Title | Office | |

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)


Electronic Submission #143461 verified by the BLM Well Information System
For NEWFIELD PRODUCTION COMPANY, sent to the Vernal

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

API Well Number: 43013515790000

Additional Operator Remarks:

SURFACE LEASE: UTU-64379
BOTTOM HOLE LEASE: UTU-16532

T9S, R16E, S.L.B.&M.

◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; Elevations are based on an N.G.S. OPUS Correction. LOCATION: LAT. 40°04'09.56" LONG. 110°00'43.28" (Tristate Aluminum Cap) Elev. 5281.57'

W-16-9-16
(Surface Location) NAD 83
LATITUDE = 40° 01' 17.85"
LONGITUDE = 110° 07' 36.83"

NEWFIELD EXPLORATION COMPANY


WELL LOCATION, W-16-9-16, LOCATED AS SHOWN IN THE NE 1/4 NW 1/4 OF SECTION 21, T9S, R16E, S.L.B.&M. DUCHESNE COUNTY, UTAH.

**NOTES:**

1. Well footages are measured at right angles to the Section Lines.
2. Bearings are based on Global Positioning Satellite observations.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.


**TRI STATE LAND SURVEYING & CONSULTING**

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

| | | |
|----------------------------|-------------------|----------|
| DATE SURVEYED: 01-10-12 | SURVEYED BY: C.S. | VERSION: |
| DATE DRAWN: 05-14-12 | DRAWN BY: M.W. | V1 |
| REVISED: 07-12-12 M.W. | SCALE: 1" = 1000' | |

T9S, R16E, S.L.B.&M.**NEWFIELD EXPLORATION COMPANY**

TARGET BOTTOM HOLE, W-16-9-16,
LOCATED AS SHOWN IN THE SE 1/4
SW 1/4 OF SECTION 16, T9S, R16E,
S.L.B.&M. DUCHESNE COUNTY, UTAH.



BASIS OF ELEV; Elevations are based on
an N.G.S. OPUS Correction. LOCATION:
LAT. 40°04'09.56" LONG. 110°00'43.28"
(Tristate Aluminum Cap) Elev. 5281.57'




= SECTION CORNERS LOCATED

**NOTES:**

1. Well footages are measured at right angles to the Section Lines.
2. Bearings are based on Global Positioning Satellite observations.
3. The Center of Pattern footages are 100' FSL & 2410' FWL.
4. The Bottom of Hole footages are 353' FSL & 2559' FWL.




THIS IS TO CERTIFY THAT THE ABOVE PERT WAS
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS
MADE BY ME OR UNDER MY SUPERVISION AND THAT
THE SAME ARE TRUE AND CORRECT TO THE BEST
OF MY KNOWLEDGE AND BELIEF.

**TRI STATE LAND SURVEYING & CONSULTING**

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

| | | |
|----------------------------|-------------------|----------|
| DATE SURVEYED: 01-10-12 | SURVEYED BY: C.S. | VERSION: |
| DATE DRAWN: 05-14-12 | DRAWN BY: M.W. | V1 |
| REVISED: 07-12-12 M.W. | SCALE: 1" = 1000' | |



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:

3160

(UT-922)

July 31, 2012

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2012 Plan of Development Greater Monument
Butte Unit, Duchesne and Uintah Counties,
Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2012 within the Greater Monument Butte Unit, Duchesne and Uintah Counties, Utah.

| API # | WELL NAME | LOCATION |
|---------------------------|----------------|------------------------------------|
| (Proposed PZ GREEN RIVER) | | |
| 43-013-51563 | GMBU H-8-9-16 | Sec 08 T09S R16E 2023 FNL 2183 FEL |
| | BHL | Sec 08 T09S R16E 1169 FNL 2473 FWL |
| 43-013-51564 | GMBU H-20-9-16 | Sec 20 T09S R16E 2110 FNL 1934 FEL |
| | BHL | Sec 20 T09S R16E 1152 FNL 2457 FWL |
| 43-013-51565 | GMBU R-8-9-16 | Sec 08 T09S R16E 0710 FSL 1908 FEL |
| | BHL | Sec 08 T09S R16E 1512 FSL 2314 FWL |
| 43-013-51566 | GMBU P-14-9-15 | Sec 15 T09S R15E 0763 FSL 0423 FEL |
| | BHL | Sec 14 T09S R15E 1561 FSL 0172 FWL |
| 43-013-51567 | GMBU M-18-9-16 | Sec 18 T09S R16E 2014 FSL 1914 FEL |
| | BHL | Sec 18 T09S R16E 2424 FNL 2307 FWL |
| 43-013-51568 | GMBU J-20-9-16 | Sec 21 T09S R16E 2041 FNL 0553 FWL |
| | BHL | Sec 20 T09S R16E 1154 FNL 0095 FEL |
| 43-013-51569 | GMBU G-21-9-16 | Sec 21 T09S R16E 2062 FNL 0557 FWL |
| | BHL | Sec 21 T09S R16E 1276 FNL 1556 FWL |
| 43-013-51570 | GMBU S-14-9-15 | Sec 14 T09S R15E 1963 FSL 0882 FEL |
| | BHL | Sec 14 T09S R15E 1068 FSL 1301 FEL |

RECEIVED: July 31, 2012

| API # | WELL NAME | LOCATION |
|---------------------------|----------------|------------------------------------|
| (Proposed PZ GREEN RIVER) | | |
| 43-013-51571 | GMBU I-18-9-16 | Sec 18 T09S R16E 1936 FNL 1914 FEL |
| | BHL | Sec 18 T09S R16E 1062 FNL 0820 FEL |
| 43-013-51572 | GMBU L-18-9-16 | Sec 18 T09S R16E 1955 FNL 1924 FEL |
| | BHL | Sec 18 T09S R16E 2485 FNL 0972 FEL |
| 43-013-51573 | GMBU H-17-9-16 | Sec 17 T09S R16E 1944 FNL 2044 FWL |
| | BHL | Sec 17 T09S R16E 0993 FNL 2432 FEL |
| 43-013-51574 | GMBU S-15-9-15 | Sec 15 T09S R15E 0768 FSL 0444 FEL |
| | BHL | Sec 15 T09S R15E 1317 FSL 1367 FEL |
| 43-013-51575 | GMBU O-13-9-15 | Sec 14 T09S R15E 1952 FSL 0864 FEL |
| | BHL | Sec 13 T09S R15E 2537 FNL 0036 FWL |
| 43-013-51576 | GMBU Q-14-9-15 | Sec 14 T09S R15E 2061 FSL 1946 FWL |
| | BHL | Sec 14 T09S R15E 1147 FSL 1132 FWL |
| 43-013-51577 | GMBU L-20-9-16 | Sec 20 T09S R16E 2117 FNL 1914 FEL |
| | BHL | Sec 20 T09S R16E 2522 FSL 1123 FEL |
| 43-013-51578 | GMBU R-14-9-15 | Sec 14 T09S R15E 2057 FSL 1967 FWL |
| | BHL | Sec 14 T09S R15E 1037 FSL 2623 FEL |
| 43-013-51579 | GMBU W-16-9-16 | Sec 21 T09S R16E 0726 FNL 1924 FWL |
| | BHL | Sec 16 T09S R16E 0353 FSL 2559 FWL |
| 43-013-51580 | GMBU L-23-9-15 | Sec 23 T09S R15E 2041 FSL 0713 FEL |
| | BHL | Sec 23 T09S R15E 2545 FNL 1706 FEL |
| 43-013-51581 | GMBU N-17-9-16 | Sec 17 T09S R16E 1965 FNL 2048 FWL |
| | BHL | Sec 17 T09S R16E 2306 FSL 1008 FWL |
| 43-013-51582 | GMBU H-21-9-16 | Sec 21 T09S R16E 0726 FNL 1945 FWL |
| | BHL | Sec 21 T09S R16E 1505 FNL 2434 FEL |
| 43-013-51587 | GMBU J-17-9-16 | Sec 16 T09S R16E 2100 FNL 0750 FWL |
| | BHL | Sec 17 T09S R16E 0988 FNL 0237 FEL |
| 43-013-51588 | GMBU J-17-9-16 | Sec 16 T09S R16E 2100 FNL 0750 FWL |
| | BHL | Sec 17 T09S R16E 0988 FNL 0237 FEL |
| 43-013-51589 | GMBU C-17-9-16 | Sec 08 T09S R16E 0704 FSL 1929 FEL |
| | BHL | Sec 17 T09S R16E 0329 FNL 2480 FWL |
| 43-013-51590 | GMBU P-24-9-15 | Sec 23 T09S R15E 2038 FSL 0692 FEL |
| | BHL | Sec 24 T09S R15E 1073 FSL 0180 FWL |

Please be advised that the GMBU J-17-9-16 has erroneously been entered twice into the UDOGM system under API Number 43-013-51587 and 43-013-51588.

This office has no objection to permitting the wells at this time.


Michael L. Coulthard

Digitally signed by Michael L. Coulthard
DN: cn=Michael L. Coulthard, o=Bureau of Land Management, ou=Branch of Minerals,
email=Michael_Coulthard@blm.gov, c=US
Date: 2012.07.31 09:41:28 -0600

bcc: File - Greater Monument Butte Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron




MCoulthard:mc:7-31-12

RECEIVED: July 31, 2012



API Number: 4301351579
Well Name: GMBU W-16-9-16
Township T09.0S Range R16.0E Section 21
Meridian: SLBM
Operator: NEWFIELD PRODUCTION COMPANY

Map Prepared:
Map Produced by Diana Mason



ON-SITE PREDRILL EVALUATION**Utah Division of Oil, Gas and Mining**

Operator NEWFIELD PRODUCTION COMPANY
Well Name GMBU W-16-9-16
API Number 43013515790000 **APD No** 6436 **Field/Unit** MONUMENT BUTTE
Location: 1/4,1/4 NENW **Sec** 21 **Tw** 9.0S **Rng** 16.0E 726 FNL 1924 FWL
GPS Coord (UTM) 574504 4430524 **Surface Owner**

Participants

Shon McKinnon - Newfield

Regional/Local Setting & Topography

New hole on existing pad. Host well is the 3-21-9-16.

Looks like pad is in good shape and see no additional situations of concern.

Surface Use Plan**Current Surface Use**

| New Road Miles | Well Pad Width Length | Src Const Material | Surface Formation |
|----------------|----------------------------|--------------------|-------------------|
|----------------|----------------------------|--------------------|-------------------|

Ancillary Facilities**Waste Management Plan Adequate?****Environmental Parameters****Affected Floodplains and/or Wetlands****Flora / Fauna****Soil Type and Characteristics****Erosion Issues****Sedimentation Issues****Site Stability Issues****Drainage Diversion Required?****Berm Required?****Erosion Sedimentation Control Required?**

| Paleo Survey Run? Resources? | Paleo Potential Observed? | Cultural Survey Run? | Cultural |
|---------------------------------|---------------------------|----------------------|----------|
|---------------------------------|---------------------------|----------------------|----------|

Reserve Pit**Site-Specific Factors****Site Ranking**

Distance to Groundwater (feet)
Distance to Surface Water (feet)
Dist. Nearest Municipal Well (ft)
Distance to Other Wells (feet)
Native Soil Type
Fluid Type
Drill Cuttings
Annual Precipitation (inches)
Affected Populations
Presence Nearby Utility Conduits
Final Score

Sensitivity Level

Characteristics / Requirements

**Closed Loop Mud Required? Liner Required? Liner Thickness Pit Underlayment
Required?**

Other Observations / Comments

Chris Jensen
Evaluator

2/13/2013
Date / Time

Application for Permit to Drill

Statement of Basis

Utah Division of Oil, Gas and Mining

| | | | | | |
|------------------|---|---------------|--------------------------|-------------------|------------|
| APD No | API WellNo | Status | Well Type | Surf Owner | CBM |
| 6436 | 43013515790000 | LOCKED | OW | S | No |
| Operator | NEWFIELD PRODUCTION COMPANY | | Surface Owner-APD | | |
| Well Name | GMBU W-16-9-16 | | Unit | GMBU (GRRV) | |
| Field | MONUMENT BUTTE | | Type of Work | DRILL | |
| Location | NENW 21 9S 16E S 726 FNL 1924 FWL GPS Coord (UTM) 574502E 4430513N | | | | |

Geologic Statement of Basis

The mineral rights for the proposed well are owned by the Federal Government. The BLM will be the agency responsible for evaluating and approving the drilling, casing and cement programs.

Brad Hill
APD Evaluator

2/26/2013
Date / Time

Surface Statement of Basis

New hole located on existing pad. Host well is the 3-21-9-16.
Looks like pad is in good shape and see no additional situations of concern.

Chris Jensen
Onsite Evaluator

2/13/2013
Date / Time

Conditions of Approval / Application for Permit to Drill

| | |
|-----------------|---|
| Category | Condition |
| Surface | The well site shall be bermed to prevent fluids from leaving the pad. |
| Surface | Drainages adjacent to the proposed pad shall be diverted around the location. |
| Surface | The reserve pit shall be fenced upon completion of drilling operations. |

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 7/16/2012

API NO. ASSIGNED: 43013515790000

WELL NAME: GMBU W-16-9-16

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 646-4825

CONTACT: Mandie Crozier

PROPOSED LOCATION: NENW 21 090S 160E

Permit Tech Review: ☒

SURFACE: 0726 FNL 1924 FWL

Engineering Review: ☐

BOTTOM: 0353 FSL 2559 FWL

Geology Review: ☒

COUNTY: DUCHESNE

LATITUDE: 40.02154

LONGITUDE: -110.12693

UTM SURF EASTINGS: 574502.00

NORTHINGS: 4430513.00

FIELD NAME: MONUMENT BUTTE

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-64379

PROPOSED PRODUCING FORMATION(S): GREEN RIVER

SURFACE OWNER: 3 - State

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

☒ PLAT☒ Bond: FEDERAL - WYB000493☐ Potash☐ Oil Shale 190-5☐ Oil Shale 190-3☐ Oil Shale 190-13☒ Water Permit: 437478☐ RDCC Review:☐ Fee Surface Agreement☐ Intent to Commingle

Commingling Approved

LOCATION AND SITING:

☐ R649-2-3.

Unit: GMBU (GRRV)

☐ R649-3-2. General☐ R649-3-3. Exception☒ Drilling Unit

Board Cause No: Cause 213-11

Effective Date: 11/30/2009

Siting: Suspends General Siting

☒ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 4 - Federal Approval - dmason
5 - Statement of Basis - bhll
15 - Directional - dmason
27 - Other - bhll

RECEIVED: February 26, 2013



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: GMBU W-16-9-16
API Well Number: 43013515790000
Lease Number: UTU-64379
Surface Owner: STATE
Approval Date: 2/26/2013

Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 213-11. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Production casing cement shall be brought up to or above the top of the unitized interval for the Greater Monument Butte Unit (Cause No. 213-11).

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the

following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels at 801-538-5284

(please leave a voicemail message if not available)

OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website

at <http://oilgas.ogm.utah.gov>

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "John Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

| | | |
|--|--|---|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-64379 |
| 1. TYPE OF WELL Oil Well | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY | | 7. UNIT or CA AGREEMENT NAME: GMBU (GRRV) |
| 3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052 | | 8. WELL NAME and NUMBER: GMBU W-16-9-16 |
| PHONE NUMBER: 435 646-4825 Ext | | 9. API NUMBER: 43013515790000 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 0726 FNL 1924 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENW Section: 21 Township: 09.0S Range: 16.0E Meridian: S | | 9. FIELD and POOL or WILDCAT: MONUMENT BUTTE |
| | | COUNTY: DUCHESNE |
| | | STATE: UTAH |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | |
| TYPE OF SUBMISSION <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 11/26/2013 <input type="checkbox"/> DRILLING REPORT Report Date: | TYPE OF ACTION <div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text"/> </div> </div> | |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. On 11/26/2013 Drill and set 5' of 14" conductor drill f/ 5' to 328' KB of 12 1/4 hole P/U and run 7 joints of 8 5/8 casing set depth 323' KB. On 11/29/13 Cement W/200 sx of G Neat cement returned 10 bbls back to pit. | | |
| NAME (PLEASE PRINT) Cherei Neilson | | PHONE NUMBER 435 646-4883 |
| SIGNATURE N/A | | TITLE Drilling Technician DATE 12/3/2013 |

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 December 03, 2013

NEWFIELD**Casing****Conductor**

| | | | | | | | | | |
|-----------------------------------|--|---|--|--------------------------------|--|-------------------------------|--|----------------------------------|--|
| Legal Well Name GMBU W-16-9-16 | | | | Wellbore Name Original Hole | | | | | |
| API/UWI 43013515790000 | | Surface Legal Location NENW 726 FNL 1924 FWL Sec 21 R16E Mer SLB | | Field Name GMBU CTB5 | | Well Type Development | | Well Configuration Type Slant | |
| Well RC 500353413 | | County Duchesne | | State/Province Utah | | Spud Date 11/26/2013 08:00 | | Final Rig Release Date | |

| | | | | | | |
|--------------------------------|--|-----------|------------------------------|---------------------------------|------------|------------|
| Wellbore | | | | | | |
| Wellbore Name Original Hole | | | | Kick Off Depth (ftKB) | | |
| Section Des | | Size (in) | Actual Top Depth (MD) (ftKB) | Actual Bottom Depth (MD) (ftKB) | Start Date | End Date |
| Conductor | | 14 | 10 | 15 | 11/26/2013 | 11/26/2013 |

| | | | |
|-----------------|--------------|---------|---------|
| Wellhead | | | |
| Type | Install Date | Service | Comment |

| | | | | |
|----------------------------|------|-------|----|--------------|
| Wellhead Components | | | | |
| Des | Make | Model | SN | WP Top (psi) |
| | | | | |

| | | | | | | | |
|---------------------------------|--|------------------------|--|------------------------|--|--------------------|--|
| Casing | | | | | | | |
| Casing Description Conductor | | Set Depth (ftKB) 15 | | Run Date 11/26/2013 | | Set Tension (kips) | |
| Centralizers | | | | Scratchers | | | |

| | | | | | | | | | | | | |
|--------------------------|---------|---------|------------|-------|------------|-----|----------|------------|------------|------------------|-------|-------------|
| Casing Components | | | | | | | | | | | | |
| Item Des | OD (in) | ID (in) | Wt (lb/ft) | Grade | Top Thread | Jts | Len (ft) | Top (ftKB) | Btm (ftKB) | Mk-up Tq (ft•lb) | Class | Max OD (in) |
| Conductor | 14 | 13.500 | 36.75 | H-40 | | 1 | 5.00 | 10.0 | 15.0 | | | |

| | | | | | | | | |
|-------------------------------|-----------------------|----------------|--------------------------|----------------------|-----------------|--------------------|---------------------|--------------------|
| Jewelry Details | | | | | | | | |
| External Casing Packer | | | | | | | | |
| Type | Setting Requirement | | | Release Requirements | | Inflation Method | Vol Inflation (gal) | Equiv Hole Sz (in) |
| Inflation Fluid Type | Infl Fl Dens (lb/gal) | P AV Set (psi) | AV Acting Pressure (psi) | P ICV Set (psi) | P ICV Act (psi) | ECP Load (1000lbf) | Seal Load (1000lbf) | |

| | | | | | | | |
|----------------------|--------------------------------|--------------------------------|-------------------------|------------------|-----------------------|--------------------------|-------------------|
| Slotted Liner | | | | | | | |
| % Open Area (%) | Perforation Min Dimension (in) | Perforation Max Dimension (in) | Axial Perf Spacing (ft) | Perf Rows | Blank Top Length (ft) | Blank Bottom Length (ft) | |
| Slot Description | Slot Pattern | | | Slot Length (in) | Slot Width (in) | Slot Frequency | Screen Gauge (ga) |

| | | | | | |
|---------------------|----------------|---------------------------|--|-----------------------|-------------------------|
| Liner Hanger | | | | | |
| Retrievable? | Elastomer Type | Element Center Depth (ft) | | Polish Bore Size (in) | Polish Bore Length (ft) |
| Slip Description | | | | Set Mechanics | |
| Setting Procedure | | | | | |
| Unsetting Procedure | | | | | |

NEWFIELD**Casing****Surface**

| | | | | | | | | | |
|-----------------------------------|--|---|--|--------------------------------|--|-------------------------------|--|----------------------------------|--|
| Legal Well Name GMBU W-16-9-16 | | | | Wellbore Name Original Hole | | | | | |
| API/UWI 43013515790000 | | Surface Legal Location NENW 726 FNL 1924 FWL Sec 21 R16E Mer SLB | | Field Name GMBU CTB5 | | Well Type Development | | Well Configuration Type Slant | |
| Well RC 500353413 | | County Duchesne | | State/Province Utah | | Spud Date 11/26/2013 08:00 | | Final Rig Release Date | |

| | | | | | | |
|--------------------------------|--|-----------|------------------------------|---------------------------------|------------|------------|
| Wellbore | | | | | | |
| Wellbore Name Original Hole | | | | Kick Off Depth (ftKB) | | |
| Section Des | | Size (in) | Actual Top Depth (MD) (ftKB) | Actual Bottom Depth (MD) (ftKB) | Start Date | End Date |
| Conductor | | 14 | 10 | 15 | 11/26/2013 | 11/26/2013 |
| Vertical | | 12 1/4 | 15 | 328 | 11/26/2013 | 11/26/2013 |

| | | | | |
|-----------------|--------------|---------|---------|--|
| Wellhead | | | | |
| Type | Install Date | Service | Comment | |

| | | | | |
|----------------------------|------|-------|----|--------------|
| Wellhead Components | | | | |
| Des | Make | Model | SN | WP Top (psi) |
| | | | | |

| | | | | | | | |
|-------------------------------|--|-------------------------|--|------------------------|--|--------------------|--|
| Casing | | | | | | | |
| Casing Description Surface | | Set Depth (ftKB) 323 | | Run Date 11/26/2013 | | Set Tension (kips) | |
| Centralizers 3 | | | | Scratchers | | | |

| | | | | | | | | | | | | |
|--------------------------|---------|---------|------------|-------|------------|-----|----------|------------|------------|------------------|-------|-------------|
| Casing Components | | | | | | | | | | | | |
| Item Des | OD (in) | ID (in) | Wt (lb/ft) | Grade | Top Thread | Jts | Len (ft) | Top (ftKB) | Btm (ftKB) | Mk-up Tq (ft•lb) | Class | Max OD (in) |
| Wellhead | 8 5/8 | 8.097 | 24.00 | J-55 | ST&C | 1 | 2.30 | 10.0 | 12.3 | | | |
| Cut off | 8 5/8 | 8.097 | 24.00 | J-55 | ST&C | 1 | 42.85 | 12.3 | 55.2 | | | |
| Casing Joints | 8 5/8 | 8.097 | 24.00 | J-55 | ST&C | 5 | 222.83 | 55.2 | 278.0 | | | |
| Float Collar | 8 5/8 | 8.097 | 24.00 | J-55 | ST&C | 1 | 1.00 | 278.0 | 279.0 | | | |
| Shoe Joint | 8 5/8 | 8.097 | 24.00 | J-55 | ST&C | 1 | 42.45 | 279.0 | 321.4 | | | |
| Guide Shoe | 8 5/8 | 8.097 | 24.00 | J-55 | ST&C | 1 | 1.50 | 321.4 | 322.9 | | | |

| | | | | | | | | | | |
|-------------------------------|-----------------------|----------------|--------------------------|----------------------|-----------------|--------------------|---------------------|--|---------------------|--------------------|
| Jewelry Details | | | | | | | | | | |
| External Casing Packer | | | | | | | | | | |
| Type | Setting Requirement | | | Release Requirements | | | Inflation Method | | Vol Inflation (gal) | Equiv Hole Sz (in) |
| Inflation Fluid Type | Infl FI Dens (lb/gal) | P AV Set (psi) | AV Acting Pressure (psi) | P ICV Set (psi) | P ICV Act (psi) | ECP Load (1000lbf) | Seal Load (1000lbf) | | | |

| | | | | | | | |
|----------------------|--------------------------------|--------------------------------|-------------------------|------------------|-----------------------|--------------------------|-------------------|
| Slotted Liner | | | | | | | |
| % Open Area (%) | Perforation Min Dimension (in) | Perforation Max Dimension (in) | Axial Perf Spacing (ft) | Perf Rows | Blank Top Length (ft) | Blank Bottom Length (ft) | |
| Slot Description | | Slot Pattern | | Slot Length (in) | Slot Width (in) | Slot Frequency | Screen Gauge (ga) |

| | | | | | |
|---------------------|----------------|---------------------------|--|-----------------------|-------------------------|
| Liner Hanger | | | | | |
| Retrievable? | Elastomer Type | Element Center Depth (ft) | | Polish Bore Size (in) | Polish Bore Length (ft) |
| Slip Description | | | | Set Mechanics | |
| Setting Procedure | | | | | |
| Unsetting Procedure | | | | | |

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Ross #29
Submitted By Branden Arnold Phone Number 435-401-0223
Well Name/Number GMBU W-16-9-16
Qtr/Qtr NE/NW Section 21 Township 9S Range 16E
Lease Serial Number UTU-64379
API Number 43-013-51579

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time 11/26/13 7:00 AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing
- ☐ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 11/26/13 3:00 AM ☐ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

RECEIVED

NOV 25 2013

DIV. OF OIL, GAS & MINING

Date/Time _____ AM ☐ PM ☐

Remarks _____

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# NDSI SS #1
Submitted By Ryan Crum Phone Number 823-7065
Well Name/Number GMBU W-16-9-16
Qtr/Qtr NE/NW Section 21 Township 9s Range 16e
Lease Serial Number UTU-64379
API Number 43-013-51579

TD Notice – TD is the final drilling depth of hole.

Date/Time 12/9/13 2:00 AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing
- ☐ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 12/9/13 12:00 AM ☐ PM ☐

RECEIVED

DEC 08 2013

DIV. OF OIL, GAS & MINING

| | | |
|---|--|---|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-64379 |
| 1. TYPE OF WELL Oil Well | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY | | 7. UNIT or CA AGREEMENT NAME: GMBU (GRRV) |
| 3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052 | | 8. WELL NAME and NUMBER: GMBU W-16-9-16 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 0726 FNL 1924 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENW Section: 21 Township: 09.0S Range: 16.0E Meridian: S | | 9. API NUMBER: 43013515790000 |
| PHONE NUMBER: 435 646-4825 Ext | | 9. FIELD and POOL or WILDCAT: MONUMENT BUTTE |
| COUNTY: DUCHESNE | | STATE: UTAH |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | |
| TYPE OF SUBMISSION | TYPE OF ACTION | |
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 1/15/2014 | <div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text"/> </div> </div> | |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between;"> <div style="width: 60%;"> The above well was placed on production on 01/15/2014 at 13:30 hours. Production Start sundry re-sent on 03/03/2014. </div> <div style="width: 35%; text-align: center;"> Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY March 04, 2014 </div> </div> | | |
| NAME (PLEASE PRINT) Jennifer Peatross | PHONE NUMBER 435 646-4885 | TITLE Production Technician |
| SIGNATURE N/A | DATE 3/3/2014 | |

Form 3160-4
(March 2012)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB NO. 1004-0137
Expires: October 31, 2014

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

| | | | | | | | | | |
|--|----------------------------|---|--------------------|--|--|--|--------------------------|-------------------|-----------------------------|
| 1a. Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Dry <input type="checkbox"/> Other | | | | | | 5. Lease Serial No. UTU64379 | | | |
| b. Type of Completion: <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Work Over <input type="checkbox"/> Deepen <input type="checkbox"/> Plug Back <input type="checkbox"/> Diff. Resvr., Other: _____ | | | | | | 6. If Indian, Allottee or Tribe Name | | | |
| 2. Name of Operator NEWFIELD PRODUCTION COMPANY | | | | | | 7. Unit or CA Agreement Name and No. UTU87538X | | | |
| 3. Address ROUTE #3 BOX 3630 MYTON, UT 84052 | | | | | 3a. Phone No. (include area code) Ph:435-646-3721 | 8. Lease Name and Well No. GMBU W-16-9-16 | | | |
| 4. Location of Well (Report location clearly and in accordance with Federal requirements)* At surface 726' FNL 1924' FWL (NE/NW) SEC 21 T9S R16E (UTU-64379) At top prod. interval reported below 34' FNL 2318' FWL (NE/NW) SEC 21 T9S R16E (UTU-64379) At total depth 373' FSL 2549' FWL (SE/SW) SEC 16 T9S R16E (UTU-16532) | | | | | | 9. API Well No. 4301351579 | | | |
| | | | | | | 10. Field and Pool or Exploratory MONUMENT BUTTE | | | |
| | | | | | | 11. Sec., T., R., M., on Block and Survey or Area SEC 21 T9S R16E Mer SLB | | | |
| 14. Date Spudded 11/26/2013 | | 15. Date T.D. Reached 12/10/2013 | | 16. Date Completed 01/10/2014 <input type="checkbox"/> D & A <input checked="" type="checkbox"/> Ready to Prod. | | 17. Elevations (DF, RKB, RT, GL)* 5980' GL 5990' KB | | | |
| 18. Total Depth: MD 6249' TVD 6100 | | 19. Plug Back T.D.: MD 6188' TVD | | 20. Depth Bridge Plug Set: MD TVD | | | | | |
| 21. Type Electric & Other Mechanical Logs Run (Submit copy of each) DUAL IND GRD, SP, COMP. NEUTRON, GR, CALIPER, CMT BOND | | | | | | 22. Was well cored? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Was DST run? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit report) Directional Survey? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes (Submit copy) | | | |
| 23. Casing and Liner Record (Report all strings set in well) | | | | | | | | | |
| Hole Size | Size/Grade | Wt. (#/ft.) | Top (MD) | Bottom (MD) | Stage Cement Depth | No. of Sks. & Type of Cement | Slurry Vol. (BBL) | Cement Top* | Amount Pulled |
| 12-1/4" | 8-5/8" J-55 | 24 | 0' | 323' | | 200 CLASS G | | | |
| 7-7/8" | 5-1/2" J-55 | 15.50 | 0' | 6234' | | 270 Econocem | | 70' | |
| | | | | | | 480Expandacem | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| 24. Tubing Record | | | | | | | | | |
| Size | Depth Set (MD) | Packer Depth (MD) | Size | Depth Set (MD) | Packer Depth (MD) | Size | Depth Set (MD) | Packer Depth (MD) | |
| 2-7/8" | EOT@5781' | TA@5680' | | | | | | | |
| 25. Producing Intervals | | | | | | | | | |
| Formation | | Top | Bottom | Perforated Interval | | Size | No. Holes | Perf. Status | |
| A) Green River | | 4110' | 5688' | 4110' - 5688' MD | | 0.34 | 60 | | |
| B) | | | | | | | | | |
| C) | | | | | | | | | |
| D) | | | | | | | | | |
| 27. Acid, Fracture, Treatment, Cement Squeeze, etc. | | | | | | | | | |
| Depth Interval | | Amount and Type of Material | | | | | | | |
| 4110' - 5688' MD | | Frac w/ 218,300#s of 20/40 white sand in 2,512 bbls of Lightning 17 fluid, in 5 stages. | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| 28. Production - Interval A | | | | | | | | | |
| Date First Produced | Test Date | Hours Tested | Test Production | Oil BBL | Gas MCF | Water BBL | Oil Gravity Corr. API | Gas Gravity | Production Method |
| 1/15/14 | 1/25/14 | 24 | → | 23 | 2 | 20 | | | 2.5 X 1.75 X 20' X 24' RHAC |
| Choke Size | Tbg. Press. Flwg. SI | Csg. Press. | 24 Hr. Rate | Oil BBL | Gas MCF | Water BBL | Gas/Oil Ratio | Well Status | |
| | | | → | | | | | PRODUCING | |
| 28a. Production - Interval B | | | | | | | | | |
| Date First Produced | Test Date | Hours Tested | Test Production | Oil BBL | Gas MCF | Water BBL | Oil Gravity Corr. API | Gas Gravity | Production Method |
| | | | → | | | | | | |
| Choke Size | Tbg. Press. Flwg. SI | Csg. Press. | 24 Hr. Rate | Oil BBL | Gas MCF | Water BBL | Gas/Oil Ratio | Well Status | |
| | | | → | | | | | | |

*(See instructions and spaces for additional data on page 2)

28b. Production - Interval C

| Date First Produced | Test Date | Hours Tested | Test Production | Oil BBL | Gas MCF | Water BBL | Oil Gravity Corr. API | Gas Gravity | Production Method |
|---------------------|----------------------|--------------|-----------------|---------|---------|-----------|-----------------------|-------------|-------------------|
| | | | → | | | | | | |
| Choke Size | Tbg. Press. Flwg. SI | Csg. Press. | 24 Hr. Rate | Oil BBL | Gas MCF | Water BBL | Gas/Oil Ratio | Well Status | |
| | | | → | | | | | | |

28c. Production - Interval D

| Date First Produced | Test Date | Hours Tested | Test Production | Oil BBL | Gas MCF | Water BBL | Oil Gravity Corr. API | Gas Gravity | Production Method |
|---------------------|----------------------|--------------|-----------------|---------|---------|-----------|-----------------------|-------------|-------------------|
| | | | → | | | | | | |
| Choke Size | Tbg. Press. Flwg. SI | Csg. Press. | 24 Hr. Rate | Oil BBL | Gas MCF | Water BBL | Gas/Oil Ratio | Well Status | |
| | | | → | | | | | | |

29. Disposition of Gas (Solid, used for fuel, vented, etc.)

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers
GEOLOGICAL MARKERS

| Formation | Top | Bottom | Descriptions, Contents, etc. | Name | Top |
|-----------|-----|--------|------------------------------|---------------------------------------|----------------|
| | | | | | Meas. Depth |
| | | | | GARDEN GULCH MARK GARDEN GULCH 1 | 3697' 3919' |
| | | | | GARDEN GULCH 2 POINT 3 | 4030' 4290' |
| | | | | X MRKR Y MRKR | 4571' 4604' |
| | | | | DOUGLAS CREEK MRK BI CARBONATE MRK | 4724' 4966' |
| | | | | B LIMESTONE MRK CASTLE PEAK | 5073' 5603' |
| | | | | BASAL CARBONATE WASATCH | 6086' 6217' |

32. Additional remarks (include plugging procedure):

33. Indicate which items have been attached by placing a check in the appropriate boxes:

- ☐ Electrical/Mechanical Logs (1 full set req'd.)
 ☐ Geologic Report
 ☐ DST Report
 ☒ Directional Survey
☐ Sundry Notice for plugging and cement verification
 ☐ Core Analysis
 ☒ Other: Drilling daily activity

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Heather CalderTitle Regulatory TechnicianSignature Heather CalderDate 02/03/2014

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 3)

(Form 3160-4, page 2)

RECEIVED: Feb. 04, 2014

NEWFIELD



NEWFIELD EXPLORATION

USGS Myton SW (UT)

SECTION 21 T9S, R16E

W-16-9-16

Wellbore #1

Design: Actual

End of Well Report

10 December, 2013





Payzone Directional
End of Well Report



API Well Number: 43013515790000

| | | | |
|------------------|----------------------|-------------------------------------|---|
| Company: | NEWFIELD EXPLORATION | Local Co-ordinate Reference: | Well W-16-9-16 |
| Project: | USGS Myton SW (UT) | TVD Reference: | W-16-9-16 @ 5992.0usft (Original Well Elev) |
| Site: | SECTION 21 T9S, R16E | MD Reference: | W-16-9-16 @ 5992.0usft (Original Well Elev) |
| Well: | W-16-9-16 | North Reference: | True |
| Wellbore: | Wellbore #1 | Survey Calculation Method: | Minimum Curvature |
| Design: | Actual | Database: | EDM 5000.1 Single User Db |

| | | | |
|--------------------|--|----------------------|----------------|
| Project | USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA | | |
| Map System: | US State Plane 1983 | System Datum: | Mean Sea Level |
| Geo Datum: | North American Datum 1983 | | |
| Map Zone: | Utah Central Zone | | |

| | | | |
|------------------------------|----------------------|--------------------------|-------------------|
| Site | SECTION 21 T9S, R16E | | |
| Site Position: | | Northing: | 7,178,195.78 usft |
| From: | Lat/Long | Easting: | 2,023,590.50 usft |
| Position Uncertainty: | 0.0 usft | Slot Radius: | 13-3/16 " |
| | | Latitude: | 40° 1' 4.650 N |
| | | Longitude: | 110° 7' 54.390 W |
| | | Grid Convergence: | 0.88 ° |

| | | | | | | |
|----------------------|---|----------|---------------------|-------------------|---------------|------------------|
| Well | W-16-9-16, SHL LAT: 40 01 17.85 LONG: -110 07 36.83 | | | | | |
| Well Position | +N/-S | 0.0 usft | Northing: | 7,179,552.14 usft | Latitude: | 40° 1' 17.850 N |
| | +E/-W | 0.0 usft | Easting: | 2,024,935.92 usft | Longitude: | 110° 7' 36.830 W |
| Position Uncertainty | | 0.0 usft | Wellhead Elevation: | 5,990.0 usft | Ground Level: | 5,980.0 usft |

| | | | | | |
|------------------|-------------------|--------------------|------------------------|----------------------|----------------------------|
| Wellbore | Wellbore #1 | | | | |
| Magnetics | Model Name | Sample Date | Declination (°) | Dip Angle (°) | Field Strength (nT) |
| | IGRF2010 | 5/14/2012 | 11.22 | 65.74 | 52,155 |

| | | | | | |
|-------------------|----------------------------|-----------------|-----------------|------------------|-----|
| Design | Actual | | | | |
| Audit Notes: | | | | | |
| Version: | 1.0 | Phase: | ACTUAL | Tie On Depth: | 0.0 |
| Vertical Section: | Depth From (TVD) (usft) | +N/-S (usft) | +E/-W (usft) | Direction (°) | |
| | 0.0 | 0.0 | 0.0 | 29.61 | |

| | | | | | |
|-----------------------|------------------|--------------------------|------------------|--------------------|--|
| Survey Program | Date | 12/10/2013 | | | |
| From (usft) | To (usft) | Survey (Wellbore) | Tool Name | Description | |
| 373.0 | 6,249.0 | Survey #1 (Wellbore #1) | MWD | MWD - Standard | |

RECEIVED: Feb. 04, 2014



Payzone Directional
End of Well Report



API Well Number: 43013515790000

Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 21 T9S, R16E
Well: W-16-9-16
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well W-16-9-16
TVD Reference: W-16-9-16 @ 5992.0usft (Original Well Elev)
MD Reference: W-16-9-16 @ 5992.0usft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey

| MD (usft) | Inc (°) | Azi (azimuth) (°) | TVD (usft) | V. Sec (usft) | N/S (usft) | E/W (usft) | DLeg (°/100usft) | Build (°/100usft) | Turn (°/100usft) |
|--------------|------------|----------------------|---------------|------------------|---------------|---------------|---------------------|----------------------|---------------------|
| 0.0 | 0.00 | 0.00 | 0.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 373.0 | 0.50 | 114.10 | 373.0 | 0.2 | -0.7 | 1.5 | 0.13 | 0.13 | 0.00 |
| 403.0 | 0.50 | 110.40 | 403.0 | 0.2 | -0.8 | 1.7 | 0.11 | 0.00 | -12.33 |
| 434.0 | 0.60 | 89.40 | 434.0 | 0.3 | -0.8 | 2.0 | 0.72 | 0.32 | -67.74 |
| 464.0 | 0.80 | 97.90 | 464.0 | 0.4 | -0.8 | 2.4 | 0.75 | 0.67 | 28.33 |
| 494.0 | 1.10 | 84.80 | 494.0 | 0.7 | -0.8 | 2.9 | 1.23 | 1.00 | -43.67 |
| 525.0 | 1.40 | 73.70 | 525.0 | 1.1 | -0.7 | 3.5 | 1.24 | 0.97 | -35.81 |
| 555.0 | 1.70 | 63.90 | 555.0 | 1.8 | -0.4 | 4.3 | 1.33 | 1.00 | -32.67 |
| 586.0 | 2.00 | 55.00 | 586.0 | 2.6 | 0.1 | 5.1 | 1.34 | 0.97 | -28.71 |
| 615.0 | 2.20 | 44.80 | 614.9 | 3.6 | 0.8 | 5.9 | 1.46 | 0.69 | -35.17 |
| 646.0 | 2.50 | 38.20 | 645.9 | 4.9 | 1.7 | 6.8 | 1.30 | 0.97 | -21.29 |
| 676.0 | 2.90 | 32.50 | 675.9 | 6.3 | 2.9 | 7.6 | 1.60 | 1.33 | -19.00 |
| 706.0 | 3.30 | 25.50 | 705.8 | 7.9 | 4.3 | 8.4 | 1.83 | 1.33 | -23.33 |
| 736.0 | 3.90 | 26.20 | 735.8 | 9.8 | 6.0 | 9.2 | 2.01 | 2.00 | 2.33 |
| 766.0 | 4.30 | 20.30 | 765.7 | 11.9 | 8.0 | 10.0 | 1.94 | 1.33 | -19.67 |
| 797.0 | 5.00 | 22.10 | 796.6 | 14.4 | 10.3 | 11.0 | 2.31 | 2.26 | 5.81 |
| 827.0 | 5.70 | 20.80 | 826.5 | 17.2 | 12.9 | 12.0 | 2.37 | 2.33 | -4.33 |
| 857.0 | 6.20 | 20.40 | 856.3 | 20.2 | 15.8 | 13.1 | 1.67 | 1.67 | -1.33 |
| 887.0 | 6.80 | 21.30 | 886.1 | 23.6 | 19.0 | 14.3 | 2.03 | 2.00 | 3.00 |
| 918.0 | 7.10 | 19.60 | 916.9 | 27.3 | 22.5 | 15.6 | 1.17 | 0.97 | -5.48 |
| 948.0 | 7.70 | 20.30 | 946.6 | 31.1 | 26.2 | 16.9 | 2.02 | 2.00 | 2.33 |
| 979.0 | 8.20 | 20.80 | 977.3 | 35.3 | 30.2 | 18.4 | 1.63 | 1.61 | 1.61 |
| 1,009.0 | 8.30 | 22.60 | 1,007.0 | 39.6 | 34.2 | 20.0 | 0.92 | 0.33 | 6.00 |
| 1,039.0 | 8.80 | 23.00 | 1,036.7 | 44.0 | 38.3 | 21.7 | 1.68 | 1.67 | 1.33 |
| 1,082.0 | 9.50 | 25.60 | 1,079.1 | 50.8 | 44.5 | 24.6 | 1.89 | 1.63 | 6.05 |
| 1,128.0 | 10.10 | 26.60 | 1,124.5 | 58.6 | 51.5 | 28.0 | 1.36 | 1.30 | 2.17 |
| 1,172.0 | 10.90 | 29.60 | 1,167.7 | 66.7 | 58.6 | 31.8 | 2.20 | 1.82 | 6.82 |

RECEIVED: Feb. 04, 2014



Payzone Directional
End of Well Report



API Well Number: 43013515790000

Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 21 T9S, R16E
Well: W-16-9-16
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well W-16-9-16
TVD Reference: W-16-9-16 @ 5992.0usft (Original Well Elev)
MD Reference: W-16-9-16 @ 5992.0usft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey

| MD (usft) | Inc (°) | Azi (azimuth) (°) | | TVD (usft) | V. Sec (usft) | N/S (usft) | E/W (usft) | DLeg (°/100usft) | Build (°/100usft) | Turn (°/100usft) |
|--------------|------------|----------------------|--|---------------|------------------|---------------|---------------|---------------------|----------------------|---------------------|
| 1,216.0 | 11.50 | 31.80 | | 1,210.9 | 75.2 | 66.0 | 36.1 | 1.67 | 1.36 | 5.00 |
| 1,262.0 | 12.30 | 30.50 | | 1,255.9 | 84.7 | 74.1 | 41.0 | 1.83 | 1.74 | -2.83 |
| 1,305.0 | 12.90 | 29.80 | | 1,297.9 | 94.1 | 82.2 | 45.8 | 1.44 | 1.40 | -1.63 |
| 1,351.0 | 13.60 | 29.60 | | 1,342.6 | 104.6 | 91.3 | 51.0 | 1.52 | 1.52 | -0.43 |
| 1,397.0 | 14.30 | 30.80 | | 1,387.3 | 115.7 | 100.9 | 56.6 | 1.65 | 1.52 | 2.61 |
| 1,441.0 | 14.80 | 30.20 | | 1,429.9 | 126.7 | 110.5 | 62.2 | 1.19 | 1.14 | -1.36 |
| 1,485.0 | 14.90 | 29.30 | | 1,472.4 | 138.0 | 120.2 | 67.8 | 0.57 | 0.23 | -2.05 |
| 1,531.0 | 15.30 | 29.30 | | 1,516.8 | 150.0 | 130.7 | 73.6 | 0.87 | 0.87 | 0.00 |
| 1,577.0 | 15.50 | 29.30 | | 1,561.2 | 162.2 | 141.3 | 79.6 | 0.43 | 0.43 | 0.00 |
| 1,620.0 | 15.60 | 28.40 | | 1,602.6 | 173.7 | 151.4 | 85.2 | 0.61 | 0.23 | -2.09 |
| 1,666.0 | 15.70 | 27.60 | | 1,646.9 | 186.1 | 162.4 | 91.0 | 0.52 | 0.22 | -1.74 |
| 1,712.0 | 15.70 | 28.10 | | 1,691.2 | 198.6 | 173.4 | 96.8 | 0.29 | 0.00 | 1.09 |
| 1,756.0 | 15.60 | 27.10 | | 1,733.5 | 210.5 | 183.9 | 102.3 | 0.65 | -0.23 | -2.27 |
| 1,802.0 | 15.50 | 27.10 | | 1,777.9 | 222.8 | 194.9 | 107.9 | 0.22 | -0.22 | 0.00 |
| 1,845.0 | 15.40 | 26.30 | | 1,819.3 | 234.2 | 205.1 | 113.1 | 0.55 | -0.23 | -1.86 |
| 1,891.0 | 14.50 | 26.20 | | 1,863.7 | 246.1 | 215.8 | 118.3 | 1.96 | -1.96 | -0.22 |
| 1,937.0 | 14.30 | 26.20 | | 1,908.3 | 257.5 | 226.0 | 123.4 | 0.43 | -0.43 | 0.00 |
| 1,981.0 | 13.90 | 27.60 | | 1,951.0 | 268.2 | 235.6 | 128.2 | 1.19 | -0.91 | 3.18 |
| 2,024.0 | 13.10 | 29.40 | | 1,992.8 | 278.2 | 244.4 | 133.0 | 2.10 | -1.86 | 4.19 |
| 2,070.0 | 11.60 | 31.80 | | 2,037.7 | 288.1 | 252.9 | 138.0 | 3.45 | -3.26 | 5.22 |
| 2,114.0 | 11.50 | 31.70 | | 2,080.8 | 296.9 | 260.4 | 142.6 | 0.23 | -0.23 | -0.23 |
| 2,158.0 | 11.40 | 30.70 | | 2,124.0 | 305.6 | 267.9 | 147.2 | 0.51 | -0.23 | -2.27 |
| 2,204.0 | 11.60 | 31.00 | | 2,169.0 | 314.8 | 275.7 | 151.9 | 0.45 | 0.43 | 0.65 |
| 2,248.0 | 11.80 | 30.40 | | 2,212.1 | 323.7 | 283.4 | 156.4 | 0.53 | 0.45 | -1.36 |
| 2,294.0 | 11.90 | 31.90 | | 2,257.1 | 333.1 | 291.5 | 161.3 | 0.70 | 0.22 | 3.26 |
| 2,340.0 | 11.70 | 33.50 | | 2,302.2 | 342.5 | 299.4 | 166.4 | 0.83 | -0.43 | 3.48 |
| 2,383.0 | 11.80 | 33.50 | | 2,344.3 | 351.2 | 306.7 | 171.2 | 0.23 | 0.23 | 0.00 |

RECEIVED: Feb. 04, 2014



Payzone Directional
End of Well Report



API Well Number: 43013515790000

| | | | |
|-----------|----------------------|------------------------------|---|
| Company: | NEWFIELD EXPLORATION | Local Co-ordinate Reference: | Well W-16-9-16 |
| Project: | USGS Myton SW (UT) | TVD Reference: | W-16-9-16 @ 5992.0usft (Original Well Elev) |
| Site: | SECTION 21 T9S, R16E | MD Reference: | W-16-9-16 @ 5992.0usft (Original Well Elev) |
| Well: | W-16-9-16 | North Reference: | True |
| Wellbore: | Wellbore #1 | Survey Calculation Method: | Minimum Curvature |
| Design: | Actual | Database: | EDM 5000.1 Single User Db |

| Survey | | | | | | | | | | |
|--------------|------------|----------------------|---------------|------------------|---------------|---------------|---------------------|----------------------|---------------------|--|
| MD (usft) | Inc (°) | Azi (azimuth) (°) | TVD (usft) | V. Sec (usft) | N/S (usft) | E/W (usft) | DLeg (°/100usft) | Build (°/100usft) | Turn (°/100usft) | |
| 2,427.0 | 12.10 | 33.50 | 2,387.3 | 360.3 | 314.3 | 176.3 | 0.68 | 0.68 | 0.00 | |
| 2,473.0 | 12.50 | 31.00 | 2,432.3 | 370.1 | 322.6 | 181.5 | 1.45 | 0.87 | -5.43 | |
| 2,519.0 | 13.00 | 31.40 | 2,477.1 | 380.3 | 331.3 | 186.7 | 1.10 | 1.09 | 0.87 | |
| 2,564.0 | 13.30 | 30.30 | 2,520.9 | 390.5 | 340.1 | 192.0 | 0.87 | 0.67 | -2.44 | |
| 2,608.0 | 13.80 | 30.20 | 2,563.7 | 400.8 | 349.0 | 197.2 | 1.14 | 1.14 | -0.23 | |
| 2,654.0 | 14.40 | 31.00 | 2,608.3 | 412.0 | 358.6 | 202.9 | 1.37 | 1.30 | 1.74 | |
| 2,698.0 | 14.60 | 30.90 | 2,650.9 | 423.0 | 368.1 | 208.5 | 0.46 | 0.45 | -0.23 | |
| 2,744.0 | 15.10 | 31.30 | 2,695.4 | 434.8 | 378.2 | 214.6 | 1.11 | 1.09 | 0.87 | |
| 2,788.0 | 15.20 | 31.30 | 2,737.9 | 446.3 | 388.0 | 220.6 | 0.23 | 0.23 | 0.00 | |
| 2,834.0 | 15.40 | 31.60 | 2,782.2 | 458.4 | 398.3 | 226.9 | 0.47 | 0.43 | 0.65 | |
| 2,879.0 | 15.60 | 32.20 | 2,825.6 | 470.5 | 408.5 | 233.3 | 0.57 | 0.44 | 1.33 | |
| 2,925.0 | 15.80 | 31.00 | 2,869.9 | 482.9 | 419.1 | 239.8 | 0.83 | 0.43 | -2.61 | |
| 2,971.0 | 15.40 | 30.20 | 2,914.2 | 495.3 | 429.8 | 246.1 | 0.99 | -0.87 | -1.74 | |
| 3,015.0 | 15.40 | 28.20 | 2,956.6 | 507.0 | 440.0 | 251.8 | 1.21 | 0.00 | -4.55 | |
| 3,060.0 | 15.40 | 27.50 | 3,000.0 | 518.9 | 450.6 | 257.4 | 0.41 | 0.00 | -1.56 | |
| 3,106.0 | 14.10 | 25.60 | 3,044.5 | 530.6 | 461.0 | 262.6 | 3.02 | -2.83 | -4.13 | |
| 3,150.0 | 14.00 | 25.40 | 3,087.2 | 541.2 | 470.7 | 267.2 | 0.25 | -0.23 | -0.45 | |
| 3,194.0 | 14.90 | 26.10 | 3,129.8 | 552.2 | 480.6 | 272.0 | 2.08 | 2.05 | 1.59 | |
| 3,238.0 | 15.50 | 27.30 | 3,172.2 | 563.7 | 490.9 | 277.2 | 1.54 | 1.36 | 2.73 | |
| 3,284.0 | 15.60 | 28.20 | 3,216.5 | 576.0 | 501.8 | 282.9 | 0.57 | 0.22 | 1.96 | |
| 3,328.0 | 15.80 | 29.60 | 3,258.9 | 587.9 | 512.2 | 288.7 | 0.97 | 0.45 | 3.18 | |
| 3,373.0 | 16.00 | 30.20 | 3,302.2 | 600.3 | 522.9 | 294.8 | 0.58 | 0.44 | 1.33 | |
| 3,419.0 | 16.40 | 30.00 | 3,346.3 | 613.1 | 534.0 | 301.3 | 0.88 | 0.87 | -0.43 | |
| 3,465.0 | 16.40 | 30.30 | 3,390.5 | 626.1 | 545.2 | 307.8 | 0.18 | 0.00 | 0.65 | |
| 3,511.0 | 16.30 | 31.10 | 3,434.6 | 639.0 | 556.3 | 314.4 | 0.54 | -0.22 | 1.74 | |
| 3,555.0 | 16.20 | 31.00 | 3,476.9 | 651.4 | 566.9 | 320.8 | 0.24 | -0.23 | -0.23 | |
| 3,600.0 | 15.70 | 30.60 | 3,520.1 | 663.7 | 577.5 | 327.1 | 1.14 | -1.11 | -0.89 | |

RECEIVED: Feb. 04, 2014



Payzone Directional End of Well Report



API Well Number: 43013515790000

Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 21 T9S, R16E
Well: W-16-9-16
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well W-16-9-16
TVD Reference: W-16-9-16 @ 5992.0usft (Original Well Elev)
MD Reference: W-16-9-16 @ 5992.0usft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey

| MD (usft) | Inc (°) | Azi (azimuth) (°) | TVD (usft) | V. Sec (usft) | N/S (usft) | E/W (usft) | DLeg (°/100usft) | Build (°/100usft) | Turn (°/100usft) |
|--------------|------------|----------------------|---------------|------------------|---------------|---------------|---------------------|----------------------|---------------------|
| 3,644.0 | 15.20 | 29.60 | 3,562.5 | 675.4 | 587.7 | 333.0 | 1.29 | -1.14 | -2.27 |
| 3,688.0 | 14.60 | 29.00 | 3,605.1 | 686.8 | 597.5 | 338.5 | 1.41 | -1.36 | -1.36 |
| 3,734.0 | 14.40 | 28.00 | 3,649.6 | 698.3 | 607.6 | 344.0 | 0.70 | -0.43 | -2.17 |
| 3,780.0 | 14.40 | 28.30 | 3,694.1 | 709.7 | 617.7 | 349.4 | 0.16 | 0.00 | 0.65 |
| 3,823.0 | 14.10 | 27.90 | 3,735.8 | 720.3 | 627.1 | 354.4 | 0.73 | -0.70 | -0.93 |
| 3,869.0 | 14.20 | 29.20 | 3,780.4 | 731.5 | 636.9 | 359.8 | 0.72 | 0.22 | 2.83 |
| 3,913.0 | 14.30 | 30.40 | 3,823.1 | 742.4 | 646.3 | 365.1 | 0.71 | 0.23 | 2.73 |
| 3,959.0 | 14.50 | 32.10 | 3,867.6 | 753.8 | 656.1 | 371.1 | 1.02 | 0.43 | 3.70 |
| 4,003.0 | 14.30 | 32.00 | 3,910.2 | 764.7 | 665.4 | 376.9 | 0.46 | -0.45 | -0.23 |
| 4,047.0 | 14.10 | 33.30 | 3,952.9 | 775.5 | 674.5 | 382.7 | 0.86 | -0.45 | 2.95 |
| 4,090.0 | 13.90 | 32.70 | 3,994.6 | 785.9 | 683.2 | 388.4 | 0.57 | -0.47 | -1.40 |
| 4,134.0 | 13.50 | 32.80 | 4,037.4 | 796.3 | 692.0 | 394.0 | 0.91 | -0.91 | 0.23 |
| 4,178.0 | 12.90 | 33.60 | 4,080.2 | 806.3 | 700.4 | 399.5 | 1.43 | -1.36 | 1.82 |
| 4,222.0 | 12.70 | 33.40 | 4,123.1 | 816.0 | 708.5 | 404.9 | 0.47 | -0.45 | -0.45 |
| 4,268.0 | 13.00 | 32.60 | 4,168.0 | 826.3 | 717.1 | 410.5 | 0.76 | 0.65 | -1.74 |
| 4,312.0 | 13.20 | 32.00 | 4,210.8 | 836.2 | 725.5 | 415.8 | 0.55 | 0.45 | -1.36 |
| 4,356.0 | 13.10 | 32.60 | 4,253.7 | 846.2 | 734.0 | 421.1 | 0.38 | -0.23 | 1.36 |
| 4,402.0 | 12.80 | 32.90 | 4,298.5 | 856.5 | 742.7 | 426.7 | 0.67 | -0.65 | 0.65 |
| 4,445.0 | 12.70 | 33.10 | 4,340.4 | 866.0 | 750.6 | 431.9 | 0.25 | -0.23 | 0.47 |
| 4,489.0 | 13.00 | 31.00 | 4,383.3 | 875.8 | 758.9 | 437.1 | 1.26 | 0.68 | -4.77 |
| 4,533.0 | 13.10 | 29.40 | 4,426.2 | 885.7 | 767.5 | 442.1 | 0.85 | 0.23 | -3.64 |
| 4,579.0 | 13.40 | 30.20 | 4,471.0 | 896.2 | 776.6 | 447.3 | 0.76 | 0.65 | 1.74 |
| 4,625.0 | 13.20 | 30.80 | 4,515.7 | 906.8 | 785.8 | 452.7 | 0.53 | -0.43 | 1.30 |
| 4,669.0 | 12.80 | 30.20 | 4,558.6 | 916.7 | 794.3 | 457.7 | 0.96 | -0.91 | -1.36 |
| 4,712.0 | 12.70 | 32.60 | 4,600.6 | 926.2 | 802.4 | 462.7 | 1.25 | -0.23 | 5.58 |
| 4,756.0 | 12.70 | 35.20 | 4,643.5 | 935.8 | 810.4 | 468.0 | 1.30 | 0.00 | 5.91 |
| 4,800.0 | 13.00 | 32.90 | 4,686.4 | 945.6 | 818.5 | 473.5 | 1.35 | 0.68 | -5.23 |

RECEIVED: Feb. 04, 2014



Payzone Directional
End of Well Report



API Well Number: 43013515790000

| | | | |
|-----------|----------------------|------------------------------|---|
| Company: | NEWFIELD EXPLORATION | Local Co-ordinate Reference: | Well W-16-9-16 |
| Project: | USGS Myton SW (UT) | TVD Reference: | W-16-9-16 @ 5992.0usft (Original Well Elev) |
| Site: | SECTION 21 T9S, R16E | MD Reference: | W-16-9-16 @ 5992.0usft (Original Well Elev) |
| Well: | W-16-9-16 | North Reference: | True |
| Wellbore: | Wellbore #1 | Survey Calculation Method: | Minimum Curvature |
| Design: | Actual | Database: | EDM 5000.1 Single User Db |

| Survey | | | | | | | | | | |
|--------------|------------|----------------------|---------------|------------------|---------------|---------------|---------------------|----------------------|---------------------|--|
| MD (usft) | Inc (°) | Azi (azimuth) (°) | TVD (usft) | V. Sec (usft) | N/S (usft) | E/W (usft) | DLeg (°/100usft) | Build (°/100usft) | Turn (°/100usft) | |
| 4,844.0 | 12.90 | 30.60 | 4,729.3 | 955.4 | 826.9 | 478.7 | 1.19 | -0.23 | -5.23 | |
| 4,888.0 | 12.60 | 30.50 | 4,772.2 | 965.2 | 835.3 | 483.6 | 0.68 | -0.68 | -0.23 | |
| 4,932.0 | 12.70 | 31.20 | 4,815.1 | 974.8 | 843.5 | 488.6 | 0.42 | 0.23 | 1.59 | |
| 4,976.0 | 12.80 | 30.30 | 4,858.0 | 984.5 | 851.9 | 493.6 | 0.51 | 0.23 | -2.05 | |
| 5,021.0 | 12.70 | 28.30 | 4,901.9 | 994.4 | 860.5 | 498.4 | 1.01 | -0.22 | -4.44 | |
| 5,065.0 | 12.90 | 27.40 | 4,944.8 | 1,004.2 | 869.2 | 503.0 | 0.64 | 0.45 | -2.05 | |
| 5,111.0 | 12.60 | 26.80 | 4,989.7 | 1,014.3 | 878.2 | 507.6 | 0.71 | -0.65 | -1.30 | |
| 5,154.0 | 12.50 | 28.20 | 5,031.7 | 1,023.6 | 886.5 | 511.9 | 0.74 | -0.23 | 3.26 | |
| 5,200.0 | 12.90 | 29.20 | 5,076.5 | 1,033.8 | 895.4 | 516.8 | 0.99 | 0.87 | 2.17 | |
| 5,246.0 | 13.10 | 27.50 | 5,121.3 | 1,044.1 | 904.5 | 521.7 | 0.94 | 0.43 | -3.70 | |
| 5,290.0 | 12.90 | 24.50 | 5,164.2 | 1,054.0 | 913.4 | 526.0 | 1.60 | -0.45 | -6.82 | |
| 5,335.0 | 12.90 | 24.20 | 5,208.1 | 1,064.0 | 922.5 | 530.2 | 0.15 | 0.00 | -0.67 | |
| 5,381.0 | 13.20 | 23.40 | 5,252.9 | 1,074.3 | 932.0 | 534.3 | 0.76 | 0.65 | -1.74 | |
| 5,425.0 | 12.50 | 22.30 | 5,295.8 | 1,084.0 | 941.0 | 538.2 | 1.69 | -1.59 | -2.50 | |
| 5,471.0 | 12.20 | 23.50 | 5,340.7 | 1,093.8 | 950.1 | 542.0 | 0.86 | -0.65 | 2.61 | |
| 5,515.0 | 12.00 | 25.20 | 5,383.8 | 1,103.0 | 958.5 | 545.8 | 0.93 | -0.45 | 3.86 | |
| 5,560.0 | 11.70 | 27.80 | 5,427.8 | 1,112.2 | 966.8 | 549.9 | 1.36 | -0.67 | 5.78 | |
| 5,606.0 | 11.30 | 27.80 | 5,472.9 | 1,121.4 | 974.9 | 554.2 | 0.87 | -0.87 | 0.00 | |
| 5,650.0 | 11.10 | 26.70 | 5,516.0 | 1,129.9 | 982.5 | 558.1 | 0.67 | -0.45 | -2.50 | |
| 5,694.0 | 11.80 | 28.30 | 5,559.2 | 1,138.6 | 990.2 | 562.1 | 1.75 | 1.59 | 3.64 | |
| 5,740.0 | 12.60 | 30.70 | 5,604.1 | 1,148.4 | 998.7 | 566.9 | 2.06 | 1.74 | 5.22 | |
| 5,784.0 | 12.90 | 29.80 | 5,647.0 | 1,158.1 | 1,007.1 | 571.8 | 0.82 | 0.68 | -2.05 | |
| 5,830.0 | 13.20 | 30.10 | 5,691.8 | 1,168.5 | 1,016.1 | 577.0 | 0.67 | 0.65 | 0.65 | |
| 5,873.0 | 13.40 | 29.30 | 5,733.7 | 1,178.3 | 1,024.6 | 581.9 | 0.63 | 0.47 | -1.86 | |
| 5,919.0 | 13.40 | 28.40 | 5,778.4 | 1,189.0 | 1,034.0 | 587.0 | 0.45 | 0.00 | -1.96 | |
| 5,965.0 | 14.00 | 29.90 | 5,823.1 | 1,199.9 | 1,043.5 | 592.3 | 1.52 | 1.30 | 3.26 | |
| 6,009.0 | 14.30 | 30.00 | 5,865.8 | 1,210.7 | 1,052.8 | 597.7 | 0.68 | 0.68 | 0.23 | |

RECEIVED: Feb. 04, 2014



Payzone Directional
End of Well Report



API Well Number: 43013515790000

| | | | |
|------------------|----------------------|-------------------------------------|---|
| Company: | NEWFIELD EXPLORATION | Local Co-ordinate Reference: | Well W-16-9-16 |
| Project: | USGS Myton SW (UT) | TVD Reference: | W-16-9-16 @ 5992.0usft (Original Well Elev) |
| Site: | SECTION 21 T9S, R16E | MD Reference: | W-16-9-16 @ 5992.0usft (Original Well Elev) |
| Well: | W-16-9-16 | North Reference: | True |
| Wellbore: | Wellbore #1 | Survey Calculation Method: | Minimum Curvature |
| Design: | Actual | Database: | EDM 5000.1 Single User Db |


| Survey | | | | | | | | | | |
|--------------|------------|----------------------|---------------|------------------|---------------|---------------|---------------------|----------------------|---------------------|--|
| MD (usft) | Inc (°) | Azi (azimuth) (°) | TVD (usft) | V. Sec (usft) | N/S (usft) | E/W (usft) | DLeg (°/100usft) | Build (°/100usft) | Turn (°/100usft) | |
| 6,055.0 | 13.70 | 30.30 | 5,910.4 | 1,221.8 | 1,062.4 | 603.3 | 1.31 | -1.30 | 0.65 | |
| 6,100.0 | 12.90 | 29.90 | 5,954.2 | 1,232.1 | 1,071.4 | 608.5 | 1.79 | -1.78 | -0.89 | |
| 6,144.0 | 12.20 | 30.10 | 5,997.2 | 1,241.7 | 1,079.7 | 613.3 | 1.59 | -1.59 | 0.45 | |
| 6,188.0 | 12.40 | 30.20 | 6,040.2 | 1,251.1 | 1,087.8 | 618.0 | 0.46 | 0.45 | 0.23 | |
| 6,249.0 | 12.40 | 30.20 | 6,099.7 | 1,264.2 | 1,099.1 | 624.6 | 0.00 | 0.00 | 0.00 | |

| | | |
|-------------------|--------------------|-------------|
| Checked By: _____ | Approved By: _____ | Date: _____ |
|-------------------|--------------------|-------------|

RECEIVED: Feb. 04, 2014





Project: USGS Myton SW (UT)
 Site: SECTION 21 T9S, R16E
 Well: W-16-9-16
 Wellbore: Wellbore #1
 Design: Actual



Azimuths to True North
 Magnetic North: 11.22°

Magnetic Field
 Strength: 52154.6snT
 Dip Angle: 65.74°
 Date: 5/14/2012
 Model: IGRF2010



Design: Actual (W-16-9-16/Wellbore #1)

Created By: *Matthew Linton* Date: 14:07, December 10 20

THIS SURVEY IS CORRECT TO THE BEST OF
 MY KNOWLEDGE AND IS SUPPORTED
 BY ACTUAL FIELD DATA

API Well Number: 43013515790000

RECEIVED: Feb. 04, 2014



Well Name: GMBU W-16-9-16

Summary Rig Activity

| | | |
|--------------|----------------|--------------|
| Job Category | Job Start Date | Job End Date |
| | | |

Daily Operations

| | | |
|---------------------------------|-------------------------------|---|
| Report Start Date 12/30/2013 | Report End Date 12/31/2013 | 24hr Activity Summary Run CBL, test csg/BOPS/vlvs and perf stg 1. |
| Start Time 00:00 | End Time 06:30 | Comment |
| Start Time 06:30 | End Time 06:45 | Comment |
| Start Time 06:45 | End Time 07:00 | Comment |
| Start Time 07:00 | End Time 09:00 | Comment Run CBL log |
| Start Time 09:00 | End Time 11:00 | Comment Pressure test csg to 4300 psi for 30 min. Test each component of the well control stack w/ low test of 250-300 psi for 5 min & high test of 4300 psi for 10 min. |
| Start Time 11:00 | End Time 12:00 | Comment Perforate stage 1 |
| Start Time 12:00 | End Time 00:00 | Comment SDFN. |
| Report Start Date 12/31/2013 | Report End Date 1/2/2014 | 24hr Activity Summary Wait on frac crew |
| Start Time 00:00 | End Time 00:00 | Comment SDFN |
| Report Start Date 1/2/2014 | Report End Date 1/3/2014 | 24hr Activity Summary Frac & flowback well |
| Start Time 00:00 | End Time 04:00 | Comment SDFN |
| Start Time 04:00 | End Time 07:00 | Comment RU Halliburton frac equipment. |
| Start Time 07:00 | End Time 07:45 | Comment Frac stg 1, CP1 sds w/ 20,000#s 20/40 white sand in 140 bbls Delta 140 17# fluid. Open pressure 0 psi. Broke @ 3561 psi w/ 2.0 bbls @ 5.7 bpm. ISDP 1611 psi, FG.:74, 1 min SIP 1402 psi. Avg rate 22.5 BPM, avg pressure 2600 psi, max rate 24.4 bpm, Max pressure 2996 psi. ISIP 1614 psi, FG.74, 5 min SIP1436 psi, 10 min SIP 1393 psi, 15 min SIP 1363 psi. |
| Start Time 07:45 | End Time 08:30 | Comment RIH w/ Weatherford 6K flow through frac plug & perf guns. Set plug @ 5270'. Perforate A1 & B2 sands. |
| Start Time 08:30 | End Time 09:00 | Comment Frac stg 2, A1 & B2 sds w/ 37,300#s 20/40 white sand in 282 bbls Delta 140 17# fluid. Open pressure 1291 psi. Broke @ 1754 psi w/ 5.0 bbls @ 5.4 bpm. ISDP 1607 psi, FG.:77. Avg rate 22.8 BPM, avg pressure 2136 psi, max rate 29.6 bpm, Max pressure 2354 psi. ISIP 1981 psi, FG.84, 5 min SIP1638 psi, 10 min SIP 1618 psi, 15 min SIP 1565 psi. |
| Start Time 09:00 | End Time 09:36 | Comment RIH w/ Weatherford 6K flow through frac plug & perf guns. Set plug @ 5020'. Perforate B.5 & C sands. |
| Start Time 09:36 | End Time 10:00 | Comment Frac stg 3, B.5 & C sds w/ 35,000#s 20/40 white sand in 234 bbls Delta 140 17# fluid. Open pressure 1422 psi. Broke @ 4169 psi w/ 4.0 bbls @ 2.0 bpm. ISDP 1535 psi, FG.:76. Avg rate 27.5 BPM, avg pressure 2609 psi, max rate 29.7 bpm, Max pressure 2871 psi. ISIP 1817 psi, FG.82, 5 min SIP1451 psi, 10 min SIP 1414 psi, 15 min SIP 1385 psi. |
| Start Time 10:00 | End Time 10:45 | Comment RIH w/ Weatherford 6K flow through frac plug & perf guns. Set plug @ 4840'. Perforate D1 & PB11 sands. |



Well Name: GMBU W-16-9-16

Summary Rig Activity

API Well Number: 43013515790000

| | | |
|--|-----------------|--|
| | | |
| Start Time | 10:45 | End Time |
| | | 11:30 |
| Comment | | |
| Frac stg 4, D1 & PB11 sds w/ 66,000#s 20/40 white sand in 483 bbls Delta 140 17# fluid. Open pressure 1205 psi. Broke @ 3751 psi w/ 10.0 bbls @ 10.9 bpm. ISDP 1469 psi, FG:77. Avg rate 21.7 BPM, avg pressure 3576 psi, max rate 24.2 bpm, Max pressure 4119 psi. ISIP 1706 psi, FG.82, 5 min SIP1543 psi, 10 min SIP 1493 psi, 15 min SIP 1468 psi. | | |
| Start Time | 11:30 | End Time |
| | | 12:00 |
| Comment | | |
| RIH w/ Weatherford 6K flow through frac plug & perf guns. Set plug @ 4350'. Perforate GB6 & GB2 sands. | | |
| Start Time | 12:00 | End Time |
| | | 12:30 |
| Comment | | |
| Frac stg 5, GB6 & GB2 sds w/ 60,000#s 20/40 white sand in 447 bbls Delta 140 17# fluid. Open pressure 1298 psi. Broke @ 1792 psi w/ 2.7 bbls @ 5.7 bpm. ISDP 1377 psi, FG:78. Avg rate 21.3 BPM, avg pressure 3421 psi, max rate 24.3 bpm, Max pressure 4168 psi. ISIP 1346 psi, FG.77, 5 min SIP1124 psi, 10 min SIP 1097 psi, 15 min SIP 1069 psi. | | |
| Start Time | 12:30 | End Time |
| | | 15:30 |
| Comment | | |
| Open well for flowback @ approx. 4 bpm. Well flowed for 2 hours & died. RU heater & tarp well head to keep from freezing. | | |
| Start Time | 15:30 | End Time |
| | | 00:00 |
| Comment | | |
| SWIFN | | |
| Report Start Date | Report End Date | 24hr Activity Summary |
| 1/3/2014 | 1/6/2014 | Set kill plug. NU drillout stack. MIRUSU. |
| Start Time | 00:00 | End Time |
| | | 06:00 |
| Comment | | |
| SDFN. | | |
| Start Time | 06:00 | End Time |
| | | 09:00 |
| Comment | | |
| RU Extreme WL truck. RIH w/ 6K solid plug. Set plug @ 4000'. Bleed pressure off well. | | |
| Start Time | 09:00 | End Time |
| | | 16:00 |
| Comment | | |
| Empty remaining fluid from frac tanks & remove tanks from location. Wait for rig to arrive | | |
| Start Time | 16:00 | End Time |
| | | 17:00 |
| Comment | | |
| Road rig to location | | |
| Start Time | 17:00 | End Time |
| | | 18:00 |
| Comment | | |
| SET BOPS W/ CRANE, SPOTTED IN PUMP/PIT,Z-TANK, REMOVED THREAD PROTECTORS ON TBG | | |
| Start Time | 18:00 | End Time |
| | | 19:00 |
| Comment | | |
| Rig up rig | | |
| Start Time | 19:00 | End Time |
| | | 20:30 |
| Comment | | |
| Crew travel | | |
| Start Time | 20:30 | End Time |
| | | 00:00 |
| Comment | | |
| SDFN | | |
| Report Start Date | Report End Date | 24hr Activity Summary |
| 1/6/2014 | 1/7/2014 | Pressure test BOPs. PU tbg & tag kill plug |
| Start Time | 00:00 | End Time |
| | | 05:30 |
| Comment | | |
| SDFN | | |
| Start Time | 05:30 | End Time |
| | | 07:00 |
| Comment | | |
| Crew travel | | |
| Start Time | 07:00 | End Time |
| | | 10:00 |
| Comment | | |
| Knight accumulator that had been delivered had a broken line on manifold. Wait for replacement accumulator | | |
| Start Time | 10:00 | End Time |
| | | 12:00 |
| Comment | | |
| Pressure test Knight double pipe rams. Testing hydraulic chambers for 5 min each w/ 3000 psi from closing unit. Pressure test pipe rams w/ low test of 250-300 psi for 5 min & high test of 5000 psi for 10 min. | | |
| Start Time | 12:00 | End Time |
| | | 14:00 |
| Comment | | |
| rebuild rig pump while waiting for pipe wrangler | | |
| Start Time | 14:00 | End Time |
| | | 17:30 |
| Comment | | |
| PU 1-4 3/4" MILL BIT, 1-REG TO EUE X-OVER SUB, 125-2 7/8" JTS TBG, TAGGED KILL PLUG @ 4000' LD 1-JT TBG, SDFN | | |



Well Name: GMBU W-16-9-16

Summary Rig Activity

API Well Number: 43013515790000

| | | |
|-------------------|-----------------|--|
| | | |
| Start Time | 17:30 | End Time |
| | | 19:00 |
| Start Time | 19:00 | End Time |
| | | 00:00 |
| Report Start Date | Report End Date | 24hr Activity Summary |
| 1/7/2014 | 1/8/2014 | Drill out kill plug & first 3 frac plugs. |
| Start Time | 00:00 | End Time |
| | | 05:30 |
| Start Time | 05:30 | End Time |
| | | 07:00 |
| Start Time | 07:00 | End Time |
| | | 10:00 |
| Start Time | 10:00 | End Time |
| | | 12:00 |
| Start Time | 12:00 | End Time |
| | | 17:00 |
| Start Time | 17:00 | End Time |
| | | 17:30 |
| Start Time | 17:30 | End Time |
| | | 19:00 |
| Start Time | 19:00 | End Time |
| | | 00:00 |
| Report Start Date | Report End Date | 24hr Activity Summary |
| 1/8/2014 | 1/9/2014 | Drill out remaining plug. Clean out to PBTD. TOO H w/ tbg & TIH w/ BHA & kill string |
| Start Time | 00:00 | End Time |
| | | 05:30 |
| Start Time | 05:30 | End Time |
| | | 07:00 |
| Start Time | 07:00 | End Time |
| | | 09:00 |
| Start Time | 09:00 | End Time |
| | | 10:30 |
| Start Time | 10:30 | End Time |
| | | 14:30 |
| Start Time | 14:30 | End Time |
| | | 15:00 |
| Start Time | 15:00 | End Time |
| | | 16:00 |
| Start Time | 16:00 | End Time |
| | | 19:00 |
| Start Time | 19:00 | End Time |
| | | 20:30 |

RECEIVED: Feb. 04, 2014



Well Name: GMBU W-16-9-16

Summary Rig Activity

API Well Number: 43013515790000

| | | | | | |
|-------------------|-----------------|--|----------|--|---|
| | | | | | |
| Start Time | | | End Time | | Comment |
| 20:30 | | | 22:00 | | Crew travel |
| Start Time | | | End Time | | Comment |
| 22:00 | | | 00:00 | | SDFN |
| Report Start Date | Report End Date | 24hr Activity Summary | | | |
| 1/9/2014 | 1/10/2014 | Continue TIH w/ tbg. Tag fill. LD extra tbg. Set TA & NU wellhead. PU rods | | | |
| Start Time | | | End Time | | Comment |
| 00:00 | | | 05:30 | | SDFN |
| Start Time | | | End Time | | Comment |
| 05:30 | | | 07:00 | | Crew Travel |
| Start Time | | | End Time | | Comment |
| 07:00 | | | 11:00 | | BLEW DOWN WELL TIH 148-JTS TBG. PU 1-JT TBG TAGGED SAND TOP @6152 LD 12-JTS TBG |
| Start Time | | | End Time | | Comment |
| 11:00 | | | 12:00 | | RU RIG FLOOR ND BOP DRILOUT STACK, MOVED DOUBLE PIPE RAMES TO NEXT WELL NIPPLED UP |
| Start Time | | | End Time | | Comment |
| 12:00 | | | 13:00 | | PREPED ROD STRING, MOVED PIPE RACKS TO NEXT WELL, UNLOADED TBG FOR NEXT WELL PT BOPS FOR NEXT WELL |
| Start Time | | | End Time | | Comment |
| 13:00 | | | 18:00 | | PU PUMP/PRIMED, PU ROD STRING AS FOLLOWS, CH 2-1/2" x 1-3/4" x 20' x 24' RHAC ROD PUMP, 30-7/8" 4PER RODS, 134- 3/4" 4PER, 1-1/2" x 30' POLISH ROD, LOADED TBG W/ 10 BBLs, STROKE TESTED UP TO 800 PSI GOOD TEST, SIWFN, DRAINED PUMP/PUMP LINES, WINTERIZED PUMP |
| Start Time | | | End Time | | Comment |
| 18:00 | | | 19:30 | | Crew Travel |
| Start Time | | | End Time | | Comment |
| 19:30 | | | 00:00 | | SDFN |
| Report Start Date | Report End Date | 24hr Activity Summary | | | |
| 1/10/2014 | 1/10/2014 | RU pumping unit. RDMOSU. | | | |
| Start Time | | | End Time | | Comment |
| 00:00 | | | 05:30 | | SDFN |
| Start Time | | | End Time | | Comment |
| 05:30 | | | 07:00 | | crew travel |
| Start Time | | | End Time | | Comment |
| 07:00 | | | 09:00 | | FOUND TAG W/ RIG, UNABLE TO GET PU STARTED, HUNG HORSE HEAD, MEASURED STROKE LENGTH, HUNG RODS IN BRIDAL |
| Start Time | | | End Time | | Comment |
| 09:00 | | | 10:30 | | RD RIG MOVED OVER TO NEXT WELL |

NEWFIELD



Schematic

43-013-51579

Well Name: GMBU W-16-9-16

| | | | | | | | |
|---|------------------|--------------------|----------------------------|-----------------------|------------------------------|-------------------|-------------------------|
| Surface Legal Location | | API/UWI | Well RC | Lease | State/Province | Field Name | County |
| NENW 726 FNL 1924 FWL Sec 21 R16E Mer SLB | | 43013515790000 | 500353413 | UTU64379 | Utah | GMBU CTB5 | Duchesne |
| Spud Date | Rig Release Date | On Production Date | Original KB Elevation (ft) | Ground Elevation (ft) | Total Depth All (TVD) (ftKB) | PBTD (All) (ftKB) | Original Hole - 6,187.5 |
| 11/26/2013 | 12/10/2013 | | 5,990 | 5,980 | Original Hole - 6,099.8 | | |

Most Recent Job

| | | | | |
|--------------------|--------------------|--------------------|----------------|--------------|
| Job Category | Primary Job Type | Secondary Job Type | Job Start Date | Job End Date |
| Initial Completion | Fracture Treatment | P&P | 12/30/2013 | 1/10/2014 |

TD: 6,249.0

Slant - Original Hole, 2/28/2014 6:30:05 AM

